

# SCIENTIFIC AMERICAN


[Entered at the Post Office of New York, N. Y., as Second Class Matter.]

A WEEKLY JOURNAL OF PRACTICAL INFORMATION, ART, SCIENCE, MECHANICS, CHEMISTRY, AND MANUFACTURES.

Vol. LVI.—No. 14.  
[NEW SERIES.]

NEW YORK, APRIL 2, 1887.

[\$3.00 per Year.]



Coronet.

Dauntless.

THE GREAT OCEAN YACHT RACE.—From a Painting by J. O. Davidson from Sketches at the Start.—[See page 213.]

# Scientific American.

ESTABLISHED 1845.

MUNN &amp; CO., Editors and Proprietors.

PUBLISHED WEEKLY AT

No. 361 BROADWAY, NEW YORK.

O. D. MUNN.

A. E. BEACH.

## TERMS FOR THE SCIENTIFIC AMERICAN.

One copy, one year, postage included..... \$3 00  
 One copy, six months, postage included..... 1 50

**Clubs.**—One extra copy of THE SCIENTIFIC AMERICAN will be supplied gratis for every club of five subscribers at \$3.00 each; additional copies at same proportionate rate. Postage prepaid.  
 Remit by postal or express money order. Address

MUNN &amp; CO., 361 Broadway, corner of Franklin Street, New York.

## The Scientific American Supplement

is a distinct paper from THE SCIENTIFIC AMERICAN. THE SUPPLEMENT is issued weekly. Every number contains 16 octavo pages, uniform in size with THE SCIENTIFIC AMERICAN. Terms of subscription for SUPPLEMENT, \$3.00 a year, postage paid, to subscribers. Single copies, 10 cents. Sold by all newsdealers throughout the country.

**Combined Rates.**—THE SCIENTIFIC AMERICAN and SUPPLEMENT will be sent for one year, postage free, on receipt of seven dollars. Both papers to one address or different addresses as desired.

The safest way to remit is by draft, postal order, express money order, or registered letter.

Address MUNN &amp; CO., 361 Broadway, corner of Franklin Street, New York.

## Scientific American Export Edition.

THE SCIENTIFIC AMERICAN Export Edition is a large and splendid periodical, issued once a month. Each number contains about one hundred large quarto pages, profusely illustrated, embracing: (1.) Most of the plates and appendices of the four preceding weekly issues of THE SCIENTIFIC AMERICAN, with its splendid engravings and valuable information; (2.) Commercial, trade, and manufacturing announcements of leading houses. Terms for Export Edition, \$5.00 a year, sent prepaid to any part of the world. Single copies, 50 cents. Manufacturers and others who desire to secure foreign trade may have large and handsomely displayed announcements published in this edition at a very moderate cost.

THE SCIENTIFIC AMERICAN Export Edition has a large guaranteed circulation in all commercial places throughout the world. Address MUNN & CO., 361 Broadway, corner of Franklin Street, New York.

NEW YORK, SATURDAY, APRIL 2, 1887.

## Contents.

(Illustrated articles are marked with an asterisk.)

|  |     |  |     |
|--|-----|--|-----|
| Absorption through the skin.....                     | 213 | Inventions, engineering.....                       | 218 |
| Account register, improved.....                      | 210 | Inventions, index of.....                          | 219 |
| Armor plates.....                                    | 216 | Inventions, miscellaneous.....                     | 214 |
| Asbestos paper.....                                  | 216 | Locusts, plague of, in Australia.....              | 215 |
| Bella, electric, Jensen.....                         | 214 | Messenger boys, paradise for.....                  | 213 |
| Black birch an ornamental wood.....                  | 210 | Moisture in rooms, increasing.....                 | 216 |
| Boiler cleaned by the Capelin.....                   | 210 | Morbid impulses.....                               | 213 |
| Boiler feed regulator.....                           | 216 | Moulding of an old fashioned knob.....             | 214 |
| Books and publications.....                          | 213 | Notes and queries.....                             | 218 |
| Boring machine, improved.....                        | 212 | Number and letter plate, improved.....             | 217 |
| Bottle attachment, Sager's.....                      | 210 | Panama Canal Works, view of.....                   | 217 |
| Business and personal.....                           | 213 | Patent laws, centennial of.....                    | 213 |
| Canal, Suez, navigation of, by night.....            | 209 | Patents, decisions relating to.....                | 213 |
| Car coupling, improved.....                          | 211 | Peach kernel oil.....                              | 213 |
| Cars, heating, by gas.....                           | 209 | Phthisis, treatment for, new.....                  | 216 |
| Carbon, manufacture of.....                          | 212 | Railway in U. S., introduction, date of.....       | 212 |
| Crane, Zenas, death of.....                          | 209 | Shall holder, improved.....                        | 217 |
| Decapitation, does consciousness continue after..... | 216 | Sham fighting sham.....                            | 210 |
| Dog, fidelity and intelligence of.....               | 211 | Ships, cemented.....                               | 210 |
| Dog story, remarkable.....                           | 212 | Solid, bulk of, measuring.....                     | 211 |
| Dogs, three related breeds of.....                   | 215 | Station indicator, for night.....                  | 217 |
| Exhibition, French, the.....                         | 209 | Steamship economy.....                             | 213 |
| Exhibition, Industrial, at Worcester, Mass.....      | 209 | Steel armor plates and gun forgings, bids for..... | 215 |
| Flowers, insects, etc., to electrolize.....          | 213 | Stove, improved.....                               | 217 |
| Furnace, hot air, Palmer's.....                      | 217 | Sugar through, at night.....                       | 217 |
| Glass tubes, cutting by electricity.....             | 211 | Sugar in the blood.....                            | 214 |
| Guns, new for the navy.....                          | 206 | Table, extension, for railway cars.....            | 210 |
| Hair spring, colored.....                            | 210 | Tash boiler fountain, Densie.....                  | 211 |
| Inventions, agricultural.....                        | 218 | Yacht race across the Atlantic.....                | 215 |

## TABLE OF CONTENTS OF SCIENTIFIC AMERICAN SUPPLEMENT No. 587.

For the Week Ending April 2, 1887.

Price 10 cents. For sale by all newsdealers.

|  |      |
|--|------|
| I. ARMS OF WAR.—The New Magazine Gun used by the German Army.—The modified Mauser gun.—The first magazine rifle introduced into any service.—4 illustrations.....  | 9073 |
| II. BIOLOGY AND PHYSIOLOGY.—Bacillus Phosphorescens.—Note on a luminous bacillus.....  | 9082 |
| Methylal.—A new anesthetic and hypnotic intermediate in effects between alcohol and ether.....   | 9078 |
| The Medico-Legal Aspects of Hypnotism.—The responsibility of a hypnotized subject as criminal or witness considered.....   | 9081 |
| The Significance of Uric Acid.—The cause of uric acid deposits.....  | 9077 |
| III. CHEMISTRY.—Fluorine by the Electrolysis of Hydrogen Fluoride.—Review of Moissan's second and third papers, giving the latest results.....   | 9075 |
| IV. ELECTRICITY.—Prof. S. P. Thompson's Dynamo Telephones.—An interesting application of the rotating dynamo armature to telephones.—2 illustrations.....  | 9079 |
| The Montand Accu-mulator.—Full description, with dimensions of this new secondary battery, and results attained by it.....   | 9070 |
| V. ENGINEERING.—Liquid Fuel.—Results obtained in petroleum firing on the Central Pacific R.R. ferryboats.—Saving effected and ratio of oil to coal in calorific value.....                                 | 9074 |
| Quick Setting Cement.—Analysis and tests of a new French cement.....   | 9073 |
| Railroads in New Regions.—An exhaustive review of American practice from a French authority.—Cars, bridges, and locomotives discussed.—11 illustrations.....   | 9070 |
| The Resistance of Slide Valves.—Experimental determination of this important factor.—Effects of diminished throw of eccentrics.—1 illustration.....  | 9069 |
| VI. GEOLOGY.—Natural Solutions of Cinnabar, Gold, and Associated sulphides.—By GEORGE F. BECKER.—A remarkable phenomenon in aqueous geology, now first discovered and described.....                       | 9080 |
| VII. NAVAL ENGINEERING.—Steam Lifeboat.—A double hulled tubular lifeboat.—Fully illustrated and described.—3 illustrations.....  | 9080 |
| The Spanish Ship of War Pelayo.—Full dimensions of this vessel, built in France for the Spanish Government, and recently launched.—Details of turret and armament.—5 illustrations.....                    | 9068 |
| VIII. PHYSICS.—On some Phenomena Connected with the Freezing of Aerated Water.—By GEORGE SHAW.—The arrangement and progressive development of bubbles in ice.—2 illustrations.....                         | 9083 |
| IX. TECHNOLOGY.—An Improvement in the Production of Sulphuric Acid.—By H. SPRENGEL, Dr. Phil. F.R.S.—Use of exhaust steam from the engines for supplying the lead chambers with steam.—1 illustration..... | 9078 |
| Improved Warming Machine.—By ROBERT HALL, Bury.—A machine adapted for the smaller class of goods.—2 illustrations.....   | 9075 |
| Manufacture of Oil of Sassafras.—By THOMAS C. HARRIS.—Simple method of conducting this process in use in North Carolina.....   | 9075 |
| The Air Brush.—A new and ingenious coloring apparatus for artists' use, the substitution of a rapid for a slow distribution of color.—Very fully described.—6 illustrations.....                           | 9076 |
| The Sulphur Industry of the United States.—By HARRY C. MYERS.—The great Utah deposits of sulphur and its occurrence elsewhere in the West.....   | 9075 |
| Vinegar.—The manufacture and preservation of vinegar.—Its local strength and qualities.....  | 9074 |
| Zincography and Zinc Printing Plates.—The process of zinc plate work, a substitute for lithography.—Inks, acids and details of management.....   | 9070 |

## SHAM FIGHTING SHAMS.

The sham sea fight now being arranged by the French naval authorities at Toulon will have an additional interest because of the controversy which followed a like engagement a year ago, when a Board of Admirals, acting as umpires, decided that the torpedo boats had won a victory over modern cruisers and great guns. The decision created no little indignation among the captains commanding the squadron engaged, not one of whom was willing to admit a successful attack on the part of the *flotte torpilleuse*.

Last year's sham battle was brought on by an attempt by torpedo boats to destroy or disperse the squadron blockading Toulon, under cover of which several fast cruisers, detained in the port, were to make their way out. As the ships could not actually be blown up, nor shell nor shot be thrown from the land works or the shipping, certain rules were agreed upon to decide when a ship or torpedo boat had been successfully attacked; the Board of Admirals deciding that when a torpedo boat was sighted through the smoke at a distance of one hundred meters, and fired upon, she should thenceforth be considered disabled and out of the fight, while, on the other hand, should she be laid aboard without that the enemy saw her, the ship was her prize as though destroyed by a torpedo.

The engagement opened at 2 A. M., at the first sign of dawn, and by the aid of his electric search lights the enemy outside was beginning to get his ranges fairly in hand, when the smoke of his guns, added to that made by the protecting shore batteries, brought down an impenetrable cloud upon the surrounding waters, and the torpedo boats, having succeeded in getting the exact compass bearing, each one that of the enemy she had singled out, together with the set of the current, dashed boldly out to the attack. When the signals from the judges' station indicated that all hands were engaged the fast cruisers, waiting with steam up for a chance to escape, sped noiselessly out.

The French commanders insist that they should have been permitted to use torpedo boats to beat off the hostile torpedo boats; and, further than this, they say that even if the torpedo boat attack was successful, the fact should not have been made public, for that it only serves to dishearten the sailors, who, let them once believe in the effectiveness of torpedo boat attack and the vulnerability of their ship, and their efficiency in time of action is sure to be seriously lessened.

This view seems, also, to be shared by the English naval authorities, who last summer, at Milford Haven, arranged a naval battle with, apparently, the single purpose of showing the bluejackets how futile is the resistance of torpedo boats to modern ships. A great boom of logs supporting heavy chains was stretched across the mouth of the harbor, and inside, presumably to protect it, a fleet of torpedo boats were gathered. The big Polyphemus, under full head, made a dash for the boom, forced it below the surface, and rode over it. Then was affixed a torpedo which tore it apart, and the enemy, in column, sailed triumphantly in.

But supposing the torpedo boats had not been carefully cooped up inside by the boom, but permitted to go out to the attack, which is their purpose—if they have any—might they not have interfered somewhat seriously with the procession?

There is reason to believe that, when the time for real work comes, the torpedo boat will prove a great surprise to the sham fighters.

## THE NEW GUNS FOR THE NAVY.

By the acts of Congress approved August 3, 1886, and March 3, 1887, the sum of \$3,120,362 is available for armament of the new vessels of the United States Navy, the monitors, cruisers, and others. The acquisition of the largest and most powerful guns made is contemplated in the granting of these appropriations. The question arises, therefore, What type of gun should be chosen? If we look abroad for a model, the heavy artillery of England, Germany, or France at once are suggested. The works of Armstrong and of Krupp, and the French establishments at Ruelle, St. Chamond, and Le Creusot, present themselves as the great gun factories of the world. Their names seem to guarantee the quality of their product. Basing their qualifications largely on the material used by these producers, the authorities of this country have called for steel of certain definite strength and ductility. The tendency is inevitably to be guided by European practice.

But criticism of this method of dealing with the question is not wanting. Facts that seem undeniable are cited which go to prove that the construction of large guns is not yet perfected. If this is true, it would suggest a field for independent work by the ordnance authorities of this country. We hardly seem justified in following blindly the lead of foreign constructors. The successful gun of the future may yet be an American production.

Many of Krupp's guns are known to have failed in war use. In the British House of Lords on April 30, 1876, the following statement was made by the Duke of

Cambridge, Commander in Chief of the British Army: "Out of seventy heavy guns employed against the southwest of Paris (by the Germans), thirty-six were disabled during the first fortnight of the bombardment by the effect of their own fire." It is said that during the Franco-Prussian war two hundred Krupp guns burst, and that the German commanders thought that a week's further resistance by the French would have silenced the batteries bombarding Paris, as the attacking guns would have become disabled by their own discharges. The Italian government has rejected two of Krupp's 100-ton guns, after trying them at Spezia.

From France, similar accounts are received of the behavior of their ordnance under more recent trials. On June 4, 1884, a 24-centimeter (9 45-100 inches) steel gun burst at Havre on the fifth round. The breech was driven backward into an earthwork at the rear, while a portion weighing several tons was driven forward, and fell into the water. Other French guns cracked near the muzzle, and had to be reduced in length. It is reported, also, that during the past year several steel guns have failed, and produced disastrous accidents in their explosions.

In England failures have been numerous. A million of pounds sterling is annually spent upon artillery. Yet *Engineering*, one of the leading English technical journals, speaking of the English artillery says: "After all this, our guns are inferior to those of other nations, and are nearly as dangerous to those who fire them as to the enemy." In 1886 the English were making five 110-ton guns, eighteen 66-ton guns, and six 43 ton guns, in the words of *Engineering*, "all on the same plan as the gun which recently failed on the Collingwood with little more than half its proper charge of powder."

In last March, in the House of Commons, the following facts were cited: To one ship orders had been sent that her guns should only be fired under reduced charges; on another ship, out of nine guns, eight were unserviceable; an 80-ton gun had been sent home from Gibraltar to be repaired; a 9-inch 18-ton gun burst at Woolwich in testing powder; 135 guns were made on one plan, and seven of these burst, requiring a lower rating of charge and reduced initial velocity for the remainder. In a letter to the London *Times* last year, Capt. Robert H. Armit referred to the disabling of all of the 38-ton guns on the Ajax, and ended his letter by stating that "there does not exist a sound gun in the service." This was only one of his letters. So far had he gone in his condemnation, that an injunction was applied for by the makers of the guns, to restrain him, which relief was refused by the court, his criticisms being held to be "privileged communications."

These are some of the lessons furnished by foreign practice. They all possess one peculiarity: they teach us how "not to do it." But we cannot say that a successful and final type of heavy gun has yet been developed. The built-up guns are subjected to strains, molecular and mechanical, that tend to their ultimate disorganization. The powder heats the metal from the interior, expanding the tube and inner rings the most. These expand, not only radially, but longitudinally. On cooling, great resistance is offered to contraction by friction, so that a permanent injury is caused in many cases. The continual expansion and shrinkage have an inevitable tendency to disorganize the whole piece. The theory of the strength of a gun teaches that the metal nearest the bore does the most work in resisting the effect of the discharge. The useful effect of the metal, according to Professor Barlow, varies inversely with the square of its distance from the longitudinal axis of the piece. Thus, the outer layers do comparatively little, and should be, if anything, the softer and more expansible metal. To be of any effect, these layers should be in intimate contact with the inner. This statement would indicate a source of weakness in re-enforced guns. A ring shrunk on may be in such a state of tension as to be ready to part, yet its connection with the tube or ring below it is not as intimate as if it were part of the same metal.

As remedies for these evils, different cures have been suggested. Soft steel of low tensile strength is advocated by one engineer. Such steel is incapable of taking a temper, and is really wrought iron. It is naturally free from many of the defects of the higher steels. The latter crack more readily, and have not the lead-like toughness of the milder metal. The lower tenacity called for seems a defect, but it is used as the index of the quality. A tough, weldable metal is inevitably of lower tenacity, and in defining this the other qualities go with it. A more radical remedy is proposed by a second engineer. He advocates the abandonment of all steel and the adoption of cast iron. This sounds like a step backward. Yet he fortifies his position with so many instances of what cast iron guns have done, that it is hard to resist the conclusion that they are at least worthy of a more extended trial. Their rifling may need special study, as the wearing of the bands has been one of their weak points. Other details may have to be worked up. But when it is considered that an integral piece is obtained at a minimum cost, the subject seems worthy of trial.

Some aluminum compounds could well be experi-

mented with. The mitis castings might afford a good basis for work. Enough has been shown to indicate a good field for inventive genius, to which we hope our government will afford every encouragement. All we wish to suggest is that the field is still open for exploration; that, according to all accounts, the perfect gun has not yet been produced.

#### Black Birch an Ornamental Wood.

Three years ago, the writer built a dwelling house in the country. In selecting the woods for the interior of the house, his attention was called to some doors the builder, Mr. P. B. Fairchild, of Orange, N. J., had put into a house he had just finished for himself. Remark- ing that I had never seen black birch used before in the inside trimming of a house, but that I liked its fine grain and the handsome color of the wood, I decided that I wanted birch used at least in one of the rooms of the house about to be built. Mr. Fairchild thought the architect might object to its use, as it was not a wood much known to the trade; and then he related how he had selected it from a lot of odds and ends of lumber lying about his shop, more to get rid of an unsalable article than for its appropriateness or its beauty, and, that his new house was built principally out of odd lots of stuff which had been accumulating for a long time about his premises.

Subsequently, an interview with the architect resulted in getting him to go and see the house finished with birch doors and trimmings, which he admitted looked very well; but then he had never heard of birch being used before for any such purpose, and he had grave misgivings as to the result of the experiment if the birch was adopted. But without further argument, the architect consented to a trial of the new wood, and it was introduced into the wainscoting, doors, and fireplace of the dining-room, and it resulted most satisfactorily to all the parties having a voice in matter—the architect, the builder, and the owner.

Persons who may not know the nature and color of black birch after dressing and polishing may be interested in knowing that the grain of the wood is very close, the color mottled and slightly darker than satin-wood. Black birch makes beautiful furniture, and the only complaint made against it for house trimmings is the care and extra time required in nailing the boards, to prevent splitting.

The above incident was brought to the writer's mind from seeing in a Western newspaper devoted to the lumber interests the following:

"The price of black birch of best quality has recently gone up from \$7 to \$95 per 1,000. The extraordinary advance is due to the discovery that boards cut out of the first logs are susceptible of a very high polish, and can be used for almost any purpose hitherto exclusively reserved for mahogany, which is worth about \$250 a thousand. The advance has been expedited by the discovery that the best black walnut is giving out. Black walnut from Arkansas and the South is so porous that it is of very little use in furniture making. The best black birch is found almost exclusively on the barren copper and ore regions between Marquette and Ashland, where all other timber is stunted in growth and very poor. Here boards cut out of the butt, quickly assume a beautiful red tint on being exposed to the atmosphere, and can be polished up to a great degree of fineness."

#### Navigation of the Suez Canal at Night.

Art. 1.—From the 1st of March, 1887, and until further orders, steamers may be permitted to navigate the canal at night under the same conditions as are in force for navigation by day, and subject to the following regulations:

Art. 2.—Steamers intending to go through the canal at night must first satisfy the agents of the company in Port Said or Port Tewfik that they are provided—  
1. Forward with an electric "projector," throwing a light 1,200 meters ahead. This projector must be placed as near as possible to the water line.

2. With an electric lamp and shade suspended above the upper deck, and powerful enough to light up a circular area of about 200 meters diameter.

3. The agents of the company will decide whether the apparatus fulfill the requirements of the regulations, so that ships provided with them may, without inconvenience, be authorized to navigate the canal at night.

Art. 3.—If a vessel, navigating by night, is ordered to get into a siding, she must, immediately on having done so, put out her electric lamps; but she must carry exclusively the regulation lights when in a siding at night, viz., forward and aft a white light, and a man on the lookout.

On the nearing of tugs, steam launches, hopper barges, etc., or of a ship empowered to pass her, she must show the side for free passage by exhibiting on such side two white lights.

Art. 4.—When two or more ships having electric lights are navigating at night in one and the same direction, and any one of them stops, she must at once hoist a red light at her mizzen-mast head, sounding

at the same time her steam whistle sharply three times in close succession, repeating this at a few moments' interval until the ship following her repeats this signal, which shall be taken as an order to slacken speed at once, with a view to stopping, if need be.

Art. 5.—Dredges working at night must carry a red light at their head as long as they are not in a siding.

Art. 6.—As soon as a ship navigating by night finds herself three miles from a dredger at work in the canal, she must signal her approach by sending up three rockets in succession. This signal must be repeated until the dredger has replied. The dredger must reply with one rocket. As soon as the dredger is in the siding, she must replace the red light at her head by a white light, and place two additional white lights on her bulwarks on the channel side.

Dredges lighted by electricity must extinguish all their electric lights as soon as they are in a siding.

Art. 7.—The signals from sidings to ships navigating at night will be as follows:

1. Slacken speed.—Three white lights one above the other.

2. Get into the siding.—Two white lights one above the other.

3. Pass on.—One white light.

When the above signals are intended for a ship coming from the north, a fixed red light will be shown above them. On the contrary, this red light will be placed below them when intended for ships coming from the south.

FERDINAND DE LESSEPS,

President-Director of the Suez Maritime Canal Universal Company.

#### Heating Cars by Gas.

In applying his skill to the heating of railway carriages, Mr. William Foulis, M. Inst. C. E., the manager in chief to the Glasgow Corporation Gas Commissioners, takes advantage of the fact that large numbers of them are already fitted with various forms of gas lamps for supplying light; and his aim has been to bring the heat that is developed in the roof of the carriage while the gas is alight down to the floor of the compartment, so as thereby to keep the feet of the passengers comfortably warm, and the whole atmosphere of the compartment at an agreeable temperature. He uses water as the medium for transmitting the heat of the gas flame from the one place to the other. A boiler is placed in the roof of the carriage over the flame of the gas lamp. It is of very simple construction, and the principle on which the heater works is that the heat from the flame comes into contact with the boiler at the point where the water is hottest and leaves it where it is coldest. From this boiler there descend two pipes about  $\frac{1}{4}$  inch in diameter, which are connected to two annular tubes placed underneath the carriage seat. The course which the two pipes take is down through the wooden partition separating the contiguous compartments. Hot water circulates through these pipes and annular tubes, and it returns to the boiler after having given off its heat. The reversal of the current is accomplished by allowing the hot water from the boiler to ascend in a tube a few inches in length, on the top of which there is a small valve. Having passed up this tube, and being unable to return to the boiler, the hot water is made to circulate downward through the pipes. The annular tubes already referred to are about  $3\frac{1}{2}$  inches in diameter and about 8 inches long. They are laid at an angle under the seat, the upper end being raised as far as practicable. The pipe which conveys the hot water is connected to the top of these tubes, and that which carries the return current is connected with the bottom of the same.

Owing to the fact that the tube is placed at an angle and that it is heated, an induced current of air is made to pass through it; and as the air enters the tube at the cold end and leaves it at the hot end, it absorbs the maximum amount of heat from the water. The air flows from these tubes or heaters in a constant stream at a temperature of from 80° to 90°. It has been found that the ordinary size of gas flame is quite sufficient to do the heating of a compartment, though the consumption of gas is less than one cubic foot per hour, and even during the coldest days of winter.

As regards the probability of the water in the apparatus freezing in cold weather when the carriage is not in use, it should be mentioned that congelation is completely prevented by mixing a given quantity of glycerine with the water. By way of testing the efficiency of this non-freezing mixture, the experimental carriage which has been placed at the service of Mr. Foulis was left exposed at night on a railway siding during the coldest weather of the past winter, without the slightest indication of freezing taking place in the water to which the glycerine had been added.

We may mention that the carriage used is a composite one of four compartments, the property of the Glasgow and Southwestern Railway Company. The internal construction of the carriage was entirely rearranged under the superintendence of Mr. Foulis. During the past two months or so, numerous experi-

mental runs have been made with this carriage as part of a regular passenger train, several of them being to and from Carlisle. On one or two occasions the patentee has been accompanied by Mr. Smellie, locomotive engineer, and other leading officials of the Glasgow and Southwestern Railway Company; and in all cases they have expressed themselves as highly satisfied with the results achieved by Mr. Foulis. The present writer had the pleasure of joining in one of the runs from Kilmarnock to Carlisle and back, when the weather was wintry in the extreme, all the hills for many miles being covered with snow. Inside the carriage the temperature was most agreeable, and in marked contrast to the outside. A thermometer hung in the compartment, in which there were only three persons, never fell below 52°, and the extent of the range was only 2°. On other occasions the temperature ranged from 56° to 60°.

Of course, in carriages heated on the "Foulis" system the gas must be constantly burning—by day as well as by night; but if heating for the comfort of the passengers is to be done, it matters not though the heat is obtained from a luminous flame, provided that it is comparatively inexpensive. In this case it is remarkably economical, while as soon as darkness sets in the gas flame does double duty, providing both heat and light. What could be more absurd than the idea of carrying gas in tanks on the cars, to warm a railway train, and what a funny idea of comfort it is to ride in a close compartment, fouled by gas jets, with a chilly temperature of 53°! *Engineering*, however, says: So far as can be seen at present, it must be unhesitatingly declared that Mr. Foulis has made a most important invention; and much credit is due to the directors of the Glasgow and Southwestern Railway Company for giving him facilities to enable him to bring it to its present perfect stage.

#### Zenas Crane.

The Dalton, Mass., Paper Mills have, for more than a generation, been among the most prominent in the country for the variety of high grade stock they turned out, under the proprietorship, and largely from the personal direction, of Zenas M. Crane, who died on the 12th ult. of apoplexy, aged 73 years. Besides fine stationery and parchments, the mill were particularly distinguished for their bank note papers, of which they made all the kinds used by the United States and several foreign governments. To Mr. Crane is attributed the idea of first introducing into the fiber of bank bills numbers corresponding to their value, to prevent the fraudulent raising of their denomination. He is said to have been dissuaded from patenting this idea, at least he never did so; but as it was largely adopted afterward, both here and abroad, his failure to obtain a patent thereon probably causes the considerable fortune he leaves to be much less than it otherwise would have been. The deceased leaves a widow and five children.

#### The French Exhibition.


In its capacity as official gazette of the Exhibition of 1889, *Le Genie Civil* gives many interesting indications of the character of the future exhibits. Among other things, an historical exhibit of methods of artificial lighting is to be prepared, showing the progress of this great modern art from the rush-light and the pine-knot torch to the first-class electric lighthouse lanterns of the present day. The buildings and grounds of the Exposition itself will furnish a striking example of the present state of the science of illumination at its height. It is decided that the main exhibition building, including the whole of the Champ de Mars, shall be fully lighted every night, leaving the palace of the Trocadero to be illuminated only by lines of exterior gas jets, as a pretty object to close the perspective view across the river. So far as the buildings themselves are concerned, everything is already being pushed to the utmost. The enormous structures of the Champ de Mars, with their roofs of two hundred and fifty feet span, are to be ready for beginning the setting of the glass roofing on the first day of next July, and in a few days the seed will be sown, in a reserved portion of the Parc aux Princes, which is to furnish turf for the *pelouses* of the Champ de Mars and the Trocadero garden. Hitherto, the grass intended to beautify the grounds about exhibition buildings has usually been either a scanty vegetation, raised on the spot from seeds sown a few weeks before, or a fictitious turf, produced by Mr. Olmsted's clever device of sowing rye and keeping it closely mown; but the Paris grass of 1889 will be cultivated by itself for two years, until it has formed a close, well-rooted sod, and will then be stripped off and transferred bodily to the place intended to receive it.—*Amer. Architect*.

#### Industrial Exhibition at Worcester, Mass.

There is now open in Worcester, Mass., at the Rink, a splendid industrial exhibition, which attracts much attention. Space and power are free to exhibitors. It is under the auspices of Mr. H. B. Bigelow, and remains open until the middle of April.

## IMPROVED ACCOUNT REGISTER.

This device is adapted for use in the keeping of accounts between a storekeeper and his customer. The case is arranged to receive and hold two sets of checks, one representing dollars and the other fractional parts of a dollar. The thickness of the checks varies in ac-



BENHAM'S ACCOUNT REGISTER.

cordance with the amount which they represent—as, for instance, the ten cent checks are twice as thick as the five cent ones, while the twenty-five cent checks are five times as thick. Each set of checks is passed upward by a spiral spring, above which is placed a block carrying a pointer ranging along a scale as shown in Fig. 1. As goods are bought, the checks representing their value are removed from the case, and pointers will then show the exact amount the customer owes in dollars and cents. For instance, Fig. 1 shows that \$16.35 have been taken out. The slate of celluloid inserted on back of Fig. 2 is for use to write orders or make out bills upon.

This invention has been patented by Luther Benham, of Marianna, Arkansas.

## IMPROVED NUMBER AND LETTER PLATE.

This number and letter plate is simple in construction and durable, and can be easily and securely attached



KIMBALL'S IMPROVED NUMBER AND LETTER PLATE.

to doors, etc. The letter plate consists of one or more plates formed on their fronts with numerals or letters, and of a dovetailed bar, Fig. 4, fitting into a corresponding groove, Figs. 2 and 3, formed on the back of each plate, which may be made either solid or box-shaped, with an open back. The bar is held to the door by screws passing through its ends. The sidewise movement of the several plates is prevented by a washer placed between each screw head and the bar, part of the edge of the washer fitting snugly against the edge of the plate. If desired, the head of the screw can perform the same function as the washer. The bar is made of varying lengths, to suit the number of plates to be united to form the required number or name.

This invention has been patented by Mr. H. Z. Kimball, of 416 Bedford Avenue, Brooklyn, N. Y.

## EXTENSION TABLE FOR RAILWAY CARS.

This extension or folding table is adapted for use at the side walls of railway cars, boats, rooms, or at the sides of house or office furniture, such as bureaus or desks. As shown in the engraving, the table is designed to fold partly against and partly within a hollow side wall of a car. The wall of the car next the floor is made hollow to provide an inner space, at the top of which is journaled a roller, over which the flexible part of the table top passes. The top consists of slats glued to a flexible backing. The outer portion of the table comprises a shelf fixed to an ornamental leg provided

with a ring or knob for drawing the table out fully into position for use. On the bottom of the leg are a roller and a couple of pins, which do not touch the floor when the leg rests on the roller; but when the table is drawn out the roller enters a recess, and the pins drop into holes in the floor. The pins prevent sidewise movement of the table, which will be thus held steadily. To the face of the wall is journaled suitably, on a vertical axis, a bracket, on which is fitted a spiral spring held at one end to the wall and at the other end to the bracket.

This spring acts normally, when the table is extended, to automatically swing the bracket outward beneath the top of the table; and as the table is pushed or folded, the bracket will be folded flat and in between the leg and wall, as the flexible top runs back over the roller and passes downward within the space in the wall. The slat at the free end of the top is a little longer than the others, to prevent the top from being drawn entirely from the opening. When the table is folded, the top and bracket are concealed from view, and the shelf may be utilized for holding various articles. It is evident that the table leg may be ornamented to correspond with the wall or piece of furniture to which it is connected.

This invention has been patented by Mr. George Schmitt, care of Delmonico's, Fifth Avenue and 26th Street, New York City.


## Cemented Ships.

Portland cement has often been described as the very life of an iron or steel ship; and considering that, as a rule, the tendency to wear and tear from corrosion is much greater on the inside than on the outside of their plating, the substance in question is, says the *Engineer*, fairly deserving of the confidence reposed in it. If the cement is good and well looked after, the inside surface of the plating from bilge to bilge can suffer no injury whatever from the usual acid water lying in the limbers. Ships have been known to "float upon their cement," one case in particular being that of an old passenger steamer, which when examined in graving dock by striking the bottom with a hammer, yielded so dead a sound at one place that a closer inspection was made, revealing the unlooked for fact that cement and not iron was being struck. The bottom plating was, indeed, wholly wasted by corrosion at the place which was struck, but so hard was the cement that only by many and vigorous blows was it broken. But cement was cement in those days, and not the adulterated mixture one sometimes comes across in this degenerate age. Moreover, sharp, fresh-water sand was used in mixing such cement as that, and not the dirty saline substitute now too commonly employed.

## HAIR SPRING COLLET.

Since 1658, when Dr. Robert Hooke, of London, invented and applied the hair spring, or balance spring (then termed pendulum spring), there has been no improvement made in the manner of fastening them to the collet. It was then, and is yet, performed by inserting the inner end into a hole drilled diagonally through the wall of the collet, and then wedged by means of a small pin. By this operation the collet would take the position that the pin or wedge had, and the inner end of the hair spring would force it to one side and make it eccentric. And as the time-keeping qualities of any time piece having a balance and hair spring depend upon the isochronal vibrations of the spring, it was necessary to bend the inner end of the spring in such a manner as to make the spring and collet concentric. This re-

quired both skill and time, and was not perfect at best. The recent invention here illustrated consists of a collet with a groove turned circularly in it the exact width of the spring and as deep as the thickness of the spring, as shown in Fig. 3. The inner coil of the spring is then sprung into this groove, which holds it absolutely central and parallel with the plane of the collet by its tension or contracting force. The collet




HUNZIKER'S HAIR SPRING COLLET.

may be formed with an annular flange only, Fig. 4, when the inner coil will be sprung over the reduced portion, and will be pressed firmly against the face of the flange. In soft springs, the inner end is inserted in a hole drilled diametrically through the wall of the collet, as shown in Fig. 5. Hardened springs hold sufficiently by the tension of the coil with the inner end.

This invention has been patented by Mr. Edward Hunziker, of 64 Nassau Street, New York City.

## BOTTLE ATTACHMENT.

The object of this invention—which has been patented by Mr. J. F. Herbert Sugg, of Sabula, Iowa—is to prevent mistakes in dispensing medicine, by bringing before the eyes of the druggist a movable label,



SUGG'S BOTTLE ATTACHMENT.


which will notify him of the nature of the contents of the bottle. Embracing the neck of the bottle is a spring clip, provided with a wire loop, upon the middle part of which is loosely pivoted a lever, formed of a wire bent spirally at its center, to form a spiral spring, which is placed on the loop. The ends of the lever extend in opposite directions, and one is secured to a plate marked with the word "poison," while the other carries a counterweight. The plate and weight are below the fulcrum, so that the lever is always in a state of stable equilibrium when the stopper is removed; and thus, when the bottle is tipped, the lever will maintain its position and allow the contents to be poured out. When the stopper is in the bottle, it holds the spring under tension, and the plate then stands vertically and presses against the stopper. When the stopper is removed, the plate is thrown forward over the mouth of the bottle by the spring. The sharp click of the plate striking the bottle calls attention to the word "poison," and, if the bottle remains in a vertical position, the plate will continue to cover the mouth and display the warning word. Should a mistake be made in dispensing the contents of the bottle, the druggist will be notified of it when he attempts to return the stopper, as the plate will be in the way, and must be removed before the stopper can be inserted. This attachment will also prevent drinking from the bottle in the dark by mistake, as it will interfere with the direct use of the bottle in that way.



SCHMITT'S EXTENSION TABLE FOR RAILWAY CARS.

## IMPROVED STOVE.

The accompanying engraving represents a stove, one-half being cut away in order to show the interior, constructed to form a fire box, three ovens, and the central main outlet flue. Within the stove are suitably arranged passages and dampers, by means of which the heat from the fire may be guided so that all of the ovens, or any one or none of them, may be especially heated. The rods by which the dampers are operated extend to the outside of the stove, within convenient reach. This stove is economical in the use of fuel, as the products of combustion, passing from one oven to



BEKOFSKY'S IMPROVED STOVE.

another, are retained a long while in the stove, so that all the available heat is utilized. The convenience of having several separate and independent ovens in each of which the degree of heat can be regulated as required is apparent.

This invention has been patented by Mr. Vladimir S. Bekofsky, Isaakieffsky, Pl. N. 15, care Restaurant, Mrs. Michel, St. Petersburg, Russia, who will furnish all further particulars.

## STATION INDICATOR FOR CARS.

This practical mechanical device is for indicating the stations on railway trains, and giving other information—such as the distance between stations, the direction the train is going, etc. The box or case is placed at any appropriate part of the car, so as to be seen by the passengers. On the front of the box the words "Next station" are painted, below which are slots, as indicated in the engraving. The names of the



CURRIE'S STATION INDICATOR FOR CARS.

stations and such other information as may be deemed necessary are printed upon a ribbon, placed close to the inner surface of the front of the box. This ribbon is wound upon suitable drums, journaled within the box, which are adapted to be revolved by a coiled spring acting through suitable gearing. The center gear is so arranged that it can be shifted to mesh either with the next upper or next lower wheel. When it engages with the upper wheel, the upper drum will be revolved in a direction to move the ribbon up; and when it engages with the lower wheel, the lower drum will be revolved to move the ribbon down or in the reverse direction. Suitable levers, engaging with notches formed in the rollers, insure the stopping of the ribbon in the proper position to display the words at the slots in the front. To start the machine in motion, these levers are lifted simultaneously by means of a rod to which their free ends are attached. When thus raised, the machine starts instantly, so that the finger piece on the lower end of the rod need be held in an elevated position only for an instant. The machine will continue to run until the points on the levers enter the notches in the rolls. It is evident that the center gear wheel need only be moved at the end of the route,

when the car will travel back over the road in the opposite direction. At each movement of the ribbon, a bell is struck to attract attention to the indicator.

This invention has been patented by Mr. William W. Currie, of Smith's Falls, Ontario, Canada.

## Measuring the Bulk of Solids.

Mr. Klummann, of Halle, has devised a simple and easily constructed little apparatus for measuring the bulk of a solid body without immersing the latter in water and without weighing it.

The instrument consists of a graduated glass tube, 1 in. in diameter, which is closed at the upper extremity with a rubber stopper, while the lower extremity is fixed in a copper box,  $\frac{3}{4}$  in. in height and 4 in. in diameter.

The apparatus is filled with sand up to the zero of the graduation. Then it is turned upside down and the bottom of the box is unscrewed, and the object inserted. After the box has been closed, it is placed in its upright position. It is then only necessary to observe the level of the sand in the tube. The volume sought for will be read upon the graduated scale.—*Chronique Industrielle*.

## Cutting Glass Tubes by Electricity.


Mr. Estere, of La Reoli, describes in *La Nature* the following process of cutting glass tubes of wide diameter by means of electricity:

The tube is surrounded with a fine wire, and the extremities of the latter are put in communication with a source of electricity. It is necessary to see that the wire adheres closely to the glass. When a current is passed through the wire, the latter becomes red hot and heats the glass beneath it. A simple drop of water deposited upon the heated place will cause a clean breakage of the glass at that point. Contrary to what happens with the usual processes, the thicker the sides of the tube are, the better the experiment succeeds. It is unnecessary to say that this process is perfectly applicable likewise to laboratory bottles.

## IMPROVED CAR COUPLING.

By means of the simple device shown in the accompanying engraving, cars may be coupled without the use of a coupling pin. In the upper surface of each drawbar, near its outer end, is formed a concave recess, inclining downward toward the extremity of the bar, and terminating in a cavity which is adapted to receive one of the balls of the coupling bar. In the recess and cavity the drawbar is slotted outwardly, and opposite the center of the cavity a flaring recess is formed in the end of the drawbar. In the bottom of the inner recess is a mortise extending downward through the drawbar. The coupling bar is a straight bar of iron, having its ends reduced in diameter, and having a ball upon each end. Coupling is effected by dropping the balls of the bar into the recesses of the drawbar, as shown in the two lower views, the lowest view being a plan. The coupling bar is held in position for coupling by standing it perpendicularly in the cavity, as indicated by the dotted lines, so that when the cars come together the jar will cause the bar to fall over and engage the empty drawbar. The drawbar may be formed with an eye at one end and ball at the other, when it is desired to use this improvement with the ordinary drawbar requiring a link and pin. The coupling bar shown in the top figure is designed to be attached to a locomotive, and is provided with a ball and eye, so that it may be used in connection with this or with the common drawbar. This device will couple on every ordinary curve and when one drawhead stands higher than the other, while the strain upon the bar is always a direct pull, no matter how sharp the curve may be, or how much difference there may be in the heights of the drawheads. In this coupling there is but one part to look after, instead of the link and two pins of the ordinary coupling.


This invention has been patented by Mr. G. R. Mavis. Particulars can be had by addressing Messrs. Mavis & Burkhalter, of Wymore, Neb.



MAVIS' IMPROVED CAR COUPLING.

## BOILER CLEANER.

The accompanying engraving represents an invention which has been patented by Mr. Albert De Camp, of Chattanooga, Tenn. The impurities in the water of the boiler are removed by a skimmer of novel form, thus preventing the formation of scale, etc. The skimmer con-




DE CAMP'S BOILER CLEANER.

sists essentially of two leaves, formed with rounded ends, and partially surrounded by upwardly extending flanges, which reach partly around the rounded ends. The sections are united by a rivet, and each is formed with a circular slot, through which a clamping bolt is passed, in order that the two leaves may be held together in any desired position. To the flange of the upper section is secured a strap having a set screw.

The skimmer is employed in connection with a blow-off attachment—illustrated in Fig. 3—in which the settling drum has a blow-off pipe provided with a valve. To the drum are secured two pipes, furnished with valves, and arranged as shown in the drawing. The skimmer is introduced through the manhole, and attached to the lower end of the shorter pipe by means of the strap and set screw.

After the skimmer has been secured, its two sections are spread apart until their ends strike the walls of the boiler, thus reaching across the water level at the rear of the boiler. As the circulation of the water is from the front to the rear end of the boiler, the impurities carried by it will be intercepted by the flanges and car-



DENNIS' WASH BOILER FOUNTAIN.

ried upward by a current passing through the short tube and into the drum, where they will settle. They may then be discharged through the blow-off pipe. The clear water at the top of the settlings passes back into the boiler through the other pipe. In Figs. 1 and 2 the leaves of the skimmer are shown extended as in use, and folded ready to be introduced through the manhole.

## WASH BOILER FOUNTAIN.

The object of this invention, which has been patented by Mr. Charles W. Dennis, of 177 Jarvis Street, Toronto, Canada, is to provide a simple device to be applied to an ordinary wash boiler, for creating a circulation of the water through the clothes in the boiler. The hollow drum is provided with a series of internal radial partitions, which extend from the inner surface of the wall of the drum toward the central aperture. A hole is formed in the drum between each pair of partitions, and the chambers between the pairs of partitions communicate with the central aperture, around which, upon the upper surface of the drum, is a collar for receiving the discharge pipe. The drum is placed in the boiler with the open side down, and the discharge pipe curves over toward the center of the boiler.

The steam from the boiling water beneath the drum carries the water up through the pipe, while the cool water enters the drum through the holes in the wall, and is heated and carried upward in the pipe. In this manner a circulation is continuously maintained, the water entering below becoming heated and rising, and then, as it becomes cool, falling and passing on its way downward through the clothes contained in the boiler. The steam is generated principally in the chambers in the drum, in which the circulation is not strong, while the body of water employed in cleansing the clothes flows continuously through the rim openings and between the pairs of partitions, and is carried upward by the steam generated in the chambers.

## DECISIONS RELATING TO PATENTS.

U. S. Circuit Court.—Southern District of New York.  
SNYDER *et al.* vs. BUNNELL *et al.*

## BURGLAR ALARM PATENT.

Coxe, J.

Where a person makes and puts on the market an article which of necessity, and to the knowledge of such person, is to be used for the purpose of infringing a patent, such person will be held liable under the doctrine of contributory infringement.

But the doctrine that a party may be held liable as an infringer solely because an article sold by him might be used by the purchaser as one element of a patented combination would be too dangerous to be upheld.

In order to hold a party liable under the doctrine of contributory infringement, there must be proof that what he did was for the purpose and with the intent of aiding infringement. (*Saxe vs. Hammond*, 1 Holmes, 456.)

Bill dismissed.

U. S. Circuit Court.—District of Massachusetts.

UNION PAPER BAG MACHINE COMPANY *et al.* vs. STANDARD PAPER BAG COMPANY *et al.*

## PAPER BAG MACHINES.

Decided November 26, 1886.

Colt, J.

Claims 8, 10, and 13 of reissued letters patent No. 8,357, July 30, 1878, for improvements in paper bag machines, by opening the end of a tubular blank and forming the first or diamond fold thereof by means of the conjoint action of two adjacent moving surfaces, these surfaces consisting of two revolving rollers into which the blank is fed, the lower roller drawing the free or lipped end of the blank in one direction, while the other roller, moving in another direction, pulls the other side of the blank by the seam connecting it with the preceding blank, this operation extending the mouth of the bag into a diamond fold shape. Held not to be infringed by defendant's machine, which has only one roller and no second divergent moving roller, the fold not being formed by the conjoint action of two diverging moving surfaces.

U. S. Circuit Court.—District of Massachusetts.

BALTIMORE CAR WHEEL COMPANY *et al.* vs. BEMIS *et al.*

Carpenter, J.

This bill alleges that the complainants are the owners of and licensees under certain letters patent for cars and car axle boxes, and that the respondents have falsely and maliciously published statements and written letters to the effect that the complainants have failed in a suit for infringement of said letters patent brought against the respondents; that the axle boxes and gear manufactured by the complainants are infringements of certain other letters patent owned by the respondents, and that suits are about to be brought by the respondents on account of such infringement against the complainants and those who shall purchase and use their axle boxes and gears. The bill further alleges that by reason of the said false statements those who desire to purchase and use the apparatus made and sold by the complainants are deterred from so doing through fear of litigation, and the business of the complainants is thereby injured, and prays for an injunction. To this bill respondents demur.

We think the demurrer is well founded. There is no jurisdiction in a court of equity to enjoin libel on the rights or title of the complainant. We understand this to be the settled law both in England and in this country, in the absence of statutory provisions conferring such jurisdiction. The question is so fully and clearly discussed in the leading decisions that we do no more than cite them. (*Prudential Assur. Co. vs. Knott*, L. R., 10 Ch., 142; *Boston Diatite Co. vs. Florence Manufg. Co.*, 114 Mass., 69; *Kidd vs. Horry*, 28 Fed. Rep., 773.)

U. S. Circuit Court.—Southern District of New York.

OSBORN vs. JUDD *et al.*

## DESIGN PATENT.

Shipman, J.

A preliminary injunction will not be granted to restrain the infringement of a "design for a banner rod, consisting of a conventional imitation of a straight twig with the bark and slantingly cut ends," the section which relates to design patents demanding, it may be supposed, the exercise of more genius than is exhibited by it.


## MORBID IMPULSES.

What is the cause of a person having a feeling as though he had to jump or throw himself down, while standing near the edge of the wall of a high building, or place 40 or 50 feet above the ground? This question is asked of the editor of the *Herald of Health*, and his answer in the journal is as follows: "This feeling is due, we think, to a sudden confusion of mind produced by the new situation in which one finds himself when brought to survey the prospect from a lofty elevation. It is a change in relation to one's surroundings that seems at first to set experience at fault, and the faculties of perception, therefore, are at

first disturbed and out of co-ordination. Size, weight, locality, etc., in many persons may require time to adjust themselves to the new conditions. Men who are accustomed to work at great elevations—roofers, painters, etc.—do not as a rule suffer from such morbid sensations, because their faculties have become educated to the relations of altitude."

## IMPROVED SHAFT HOLDER.

Pivotaly connected to the shafts, at the left hand side of the vehicle, is a bar shaped as clearly shown in the side elevation, Fig. 2. One end of this bar extends forward along the shaft, and is pressed upward




SPENNEBERG'S IMPROVED SHAFT HOLDER.

by a spring, while the other end is formed with a pawl, so that it may engage with a serrated plate secured to the rear side of the axle by the clip bolts. When the shafts are raised to the desired height, they will be caught and held in that position by the pawl engaging with one of the serrations of the plate. They will then be out of the way, and there will be no danger of their being broken. To lower the shafts into position for harnessing the horse, it is only necessary to press upon the outer end of the bar to detach the pawl, when they will come down gradually and without noise. This simple and efficient device will be appreciated by carriage owners, because of its many excellent features.

This invention has been patented by Mr. G. J. Spenneberg. Further particulars can be had from Mr. J. A. Donaldson, of Carrollton, Ky.

## IMPROVED BORING MACHINE.

The boring machine illustrated in the accompanying engraving has many admirable features. When once placed in position, it will bore the whole mortise without being moved, thereby doing double the amount of work in the same length of time, and with greater ease to the operator, as the cranks are adjustable for large or small auger, soft or hard wood, and any speed may



DRYDEN'S IMPROVED BORING MACHINE.

be given to the auger. The machine is moved horizontally by means of the side screw, which is cut with two threads to the inch, and thereby forms a gauge. The machine may be adjusted to bore at any required angle. It will bore two or more holes to the same depth, as it has a stop provided for that purpose. The machine is compact, simple in construction, and efficient.

It is manufactured solely by Mr. George W. Dryden, of 23 Glen Street, Worcester, Mass., and may be seen at the Worcester (Mass.) Industrial Exhibition.

## New Treatment for Phthisis.

A new method of treating phthisis has been proposed, but apparently as yet but slightly tried, by Professor Kremianski, who read a paper on the subject at the recent Moscow Medical Congress, which provoked a good deal of discussion. The idea is based, first, on the fatal effect of the most dilute solution of aniline on Koch's bacillus, and, secondly, on the fact that aniline seems to be but slightly, if at all, poisonous to the human body. Professor Kremianski proposes to introduce aniline into the lungs, and, indeed, the circulation generally, by inhalation, so that the phthisis bacilli would be bathed in a very dilute solution of aniline, wherever they may be. This, he thinks, would kill them, and render even pulmonary cavities free from bacilli, so bringing them into the condition of healthy granulating ulcers, which may be expected to cicatrize. A committee has been appointed, including Professors Subbotin and Ostroumoff, who expressed themselves at the meeting as strongly opposed to the plan, for the purpose of observing Professor Kremianski's proposed experiments in one of the Moscow hospitals.

Two cases in which the aniline treatment had been successfully tried were detailed. A lad of eighteen, who had undoubted phthisis, was ordered a four drop dose of aniline (but took by mistake three times the proper quantity) combined with nux vomica, mint water, and antifebrin, his diet being good, including dried meat, kvas, and oranges. He was also given inhalations of atomized aniline. A remarkable change took place almost immediately, all the rales disappearing; his temperature, respiration, and pulse becoming normal. His skin, however, assumed a slightly blue tinge; but whether this was as permanent as the cure is represented to have been is not stated.

The second case was a complicated one, there being tubercular peritonitis and meningitis, together with typhoid fever, present at the same time as pulmonary phthisis. Aniline inhalations, washing out the pulmonary cavities with corrosive sublimate and antifebrin, were employed, together with a special acid diet, as in the other case. Here, too, the results are said to have been remarkably good, the bacilli disappearing from the sputum, and the patient regaining his health entirely. No mention is made in the abstract published by the *Vrach* of any change of color in this patient's skin.

Among the various replies that were made to Professor Kremianski, Dr. Zakrzhevski, of Helsingfors, remarked that, admitting the facts as stated, still there was nothing to show that the aniline had been the cause of the cures. He himself had had surprisingly good results in phthisical cases, the disease becoming completely arrested by simply giving increased nourishment and prescribing antipyrin.—*Lancet*.

## Manufacture of Carbon.

The following item, says a correspondent in the *Electrical World*, I have picked up, and it ought to be of interest:

"The manufacture of carbons for electric lights has become an important business. At a trial in Cleveland for alleged infringement of patent, a witness testified that of 150,000 carbons burned daily in the United States, 100,000 are manufactured in Cleveland, where there are 20 furnaces. The carbons are made chiefly of the residuum of oil after it has been refined, but the deposit about natural gas wells is also coming into use. The material is ground to a powder, a little pitch is added, and the substance is then placed in moulds. These are packed in boxes and the latter placed in a furnace, where they are subjected to the most intense heat. The capacity of an ordinary furnace is 45,000 carbons. Through the use of a movable furnace roof, the patent on which forms the subject of contention, two furnaces are constructed side by side, and while the carbons in one are being burned the other is loaded with boxes of moulds. Under this system two men load a furnace in one day, the carbons are thoroughly burned in five days, and the cooling process continues only 24 hours."

## A Remarkable Dog Story.

John Templeton is a blacksmith who owns a fine specimen of the English mastiff. Recently Mr. Templeton was working at his forge, putting a new steel in a pick. The new steel was slightly burned in the heating, and, instead of welding, flew in half a dozen pieces. One piece struck the blacksmith just above the right eye with such force as to fasten itself in firmly. The blacksmith staggered and fell backward. How long he was unconscious he does not know, but when he revived the dog lay almost in the middle of the shop crying almost like a human being, and rubbing his jaws in the dust of the floor. The piece of steel that had struck Mr. Templeton lay a short distance from the dog. The faithful brute had seized the hot steel with his teeth and drawn it from the frontal bone of Mr. Templeton's head. The dog's mouth was found to be badly burned.—*Albany Journal*.

## YACHT RACE ACROSS THE ATLANTIC.

On March 12, the transatlantic yacht race from Owl's Head, New York harbor, to Roche's Point, Queenstown harbor, was started. Up to the present writing (March 26), the relative position of the two competing yachts is unknown, as the reports brought in by the steamers are vague and conflicting. It therefore seems probable that the first authentic information will be sent out when the winner crosses the finish. Quick time is not looked for, owing to heavy seas and adverse winds.

The race is the result of a challenge issued by the owner of the *Coronet*, and is "for the purpose of testing and comparing the sea-going and sailing qualities of keel-schooner yachts built and now owned in this country." The race was open to all yachts of this description of American build, without any allowance whatever. This challenge was accepted by the owner of the *Dauntless*, and each yacht put up \$10,000, so that the winner will receive double this amount, less incidental expenses.

The principal dimensions of the two yachts are given below:

|  | <i>Coronet.</i> | <i>Dauntless.</i> |
|--|-----------------|-------------------|
|  | Ft. In.         | Ft. In.           |
| Length over all.....   | 133 0           | 134 0             |
| Length on load water line.....   | 123 0           | 117 7             |
| Extreme beam.....  | 27 0            | 26 7              |
| Extreme draught of water.....  | 12 6            | 12 3              |
| Least freeboard.....   | 3 6             | 3 7               |
| Length of mainmast.....  | 91 0            | 85 6              |
| Length of main boom.....   | 68 0            | 68 0              |
| Length of topmast.....   | 36 0            | 46 0              |
| Perpendicular of sail triangle, as per New York Yacht Club rule.....   | 108 0           | 107 0             |
| Base of sail triangle, as per New York Yacht Club rule.....            | 184 9           | 183 6             |
| Sail tons, as per New York Yacht Club rule for racing measurement..... | 114             | 111.2             |
| Area of lower sails in square feet.....                                | 7,135           | 6,941             |
| Area of top sails in square feet.....                                  | 1,130           | 1,068             |
| Area of square sails in square feet.....                               | 3,135           | 2,865             |
| Load displacement in tons.....   | 277             | 215               |
| Ballast in tons.....   | 126             | 80                |
| Tonnage, old measurement.....  | 350             | 267.7             |

The *Coronet* is considered to have two distinct advantages over her rival—she is larger and newer. She was built by the Poillon Brothers, at South Brooklyn, in 1885, while the *Dauntless* was constructed twenty-one years ago, at Mystic Bridge, Conn., by Forsyth & Morgan.

The *Coronet* crossed the finish line first, at 12:41 P. M., Queenstown time, on March 27th. Her time is next to the best ever made by a yacht from New York to Queenstown, and is especially remarkable as the weather, during the entire voyage, was uncommonly tempestuous, even for this season of the year. The actual time from the start was 14 days 19 hours 3 minutes and 14 seconds. The whole number of nautical miles sailed was 2,934. The longest day's run, 291.5 miles, was made on the 26th, and the two shortest, 39 and 51 miles, on the 22d and 23d respectively.

The *Dauntless* was sighted at 11 A. M. on the 28th.

## How to Electroplate Flowers, Insects, Etc.

Among the most recent efforts in this direction may be mentioned the improvements in the preparation of organic matter for metallization by galvanic deposit recently introduced by La Societe anonyme de Metallisation artistique des Animaux, Vegetaux, ou autres corps, of Paris, whose process consists in the employment of an albuminous liquid, with which the different substances in question are treated to prepare them for metallization. This liquid may be thus obtained: A quantity of snails or slugs are first washed in ordinary water, to free them from all earthy or calcareous matter; they are then placed in a vessel containing distilled water, and are left here sufficient time to give off slowly their albuminous matter.

The albumen thus obtained is now filtered and boiled for about an hour. After the boiling is added a quantity of distilled water sufficient to replace that lost by the boiling, and about 3 per cent of nitrate of silver. This liquid is then placed in bottles, hermetically closed, and kept in the dark; it will thus keep without any alteration. To use this liquid for the preparation of the objects, about 30 grammes of it is dissolved in about 100 grammes of distilled water. In this solution the objects are submerged for a few moments; they are then placed in a bath consisting of distilled water with about 20 per cent of nitrate of silver in solution, and afterward submitted to the action of hydrosulphuric gas, to reduce the nitrate of silver adhering to the albumen-covered surface of the object.

Thus treated, all organic matter is rendered fit to receive a galvanic deposit; and the galvanic products obtained by this process are far superior in fineness and neatness to those obtained by any other known process. Even the finest and most minute fibers and veins, the smallest unevenness of surfaces, and hairs scarcely visible to the naked eye are clearly discernible, and come out with striking neatness, the metallic deposit being of perfectly uniform thickness and adherence.

## Steamship Economy.

At a recent meeting of the Engineering Section of the Bristol Naturalists' Society, a paper on "Compound- ing Oscillating Marine Engines," of which the following is a summary, was read by Mr. J. W. J. Harvey:

In describing the method adopted, attention was called to the fact that in the search after economy the history of these engines is somewhat unique, if not altogether exceptional, from the circumstance that no less than three separate classes of engines had been at work in the same vessel—the *Juno*—viz., "jet condensing," "surface condensing," and "compound," under almost identical conditions of "draught of water," "displacements," "midship area," "propeller," etc., from which probably may be drawn some useful conclusions as to the cost of motive power in steam vessels, having regard to the description of machinery employed. With the "jet condensing" engines, working with a boiler pressure of 30 lb. per square inch, an indicated horse power of 1,605 was developed on a consumption of 92 tons of coal per voyage, giving the vessel a speed of 14.1-10 knots per hour. Subsequently the engines were fitted with a surface condenser and new boilers working at the original pressure of 30 lb. per square inch, when the same indicated horse power and speed were maintained on a reduced consumption of 84½ tons of coal per voyage.

At the time the above alterations were made—although it was seriously under consideration to fit the vessel with compound engines—the competition was not so keen as to warrant the heavy outlay such a change would have involved, and recourse was therefore had to the surface condensing arrangement. In process of time it is scarcely necessary to be reminded that competition in the shipping trade had become much more severe, so that the vessel had to compete with others in the same trade more recently built and fitted with compound machinery, and it is evident that she would be out of the race unless a considerable reduction could be made in the coal bill. The vessel was too good and too great a favorite to be cast aside as obsolete; and as the outlay for entirely new compound machinery would not have been justifiable, it was determined to compound the existing engines at as moderate a cost as possible, at the same time maintaining such a rate of speed as would enable her to hold her own with her more modern rivals. In carrying out this idea it was necessary to retain as much of the existing machinery as possible, and to do this it was determined to keep one of the existing cylinders as the low pressure cylinder of the compound arrangement, and to so proportion the new high pressure cylinder as to obtain the maximum power possible, and by this means the greater part of the existing machinery was preserved, one cylinder, the entablatures, shafts, paddle wheels, condenser, side frames, air, circulating, and bilge pumps being retained, and the new parts required consisted only of one cylinder, two sets of link motion, two feed pumps, a steam starting engine, and, of course, a pair of cylindrical boilers working at 80 lb. pressure. The result was a compound engine having cylinders 40 in. and 66 in. diameter by 72 in. stroke, giving 1,270 indicated horse power, and a speed of 13.4-10 knots per hour, on a consumption of 49 tons of coal per voyage, the conditions as to draught of water, etc., remaining the same as before. The conclusions to be drawn are, therefore, that with 335 less indicated horse power, we have the loss of three-quarters of a knot in speed, or, in other words, it takes 335 indicated horse power to get the last three-quarters of a knot, or about one-fifth of the whole power; that, when working with the jet condenser, the coal consumption was 92 tons per voyage. When working with the surface condenser, the consumption was 84½ tons per voyage, or a saving of 8½ per cent; and when compounded, the consumption was 49 tons per voyage, giving a saving of 46½ per cent over the jet condenser, and 43 per cent over the surface condenser. This result was deemed highly satisfactory, and has enabled the vessel to compete successfully with those of a more modern type, and to retain her place on the line in which, through all weathers and seasons, she has established for herself a favorable and widespread reputation.

## Peach Kernel Oil.

M. P. Guyot (*Rep. de Pharm.*) gives the following tests for oil of peach kernels:

With caustic alkalis it gives a dark yellowish-brown soap, easily soluble in distilled water. With phosphoric acid, at first a yellowish-brown emulsion, which becomes gray and then loses its color. Chloride of zinc forms dirty gray flocks in the liquid; and sulphuric acid, an orange-yellow coloration, passing through various shades of brown and red to a dark brown, the oil giving off a distinct odor of oil of bitter almonds as soon as it becomes warm. Sulphocarbonate of sodium affords an orange-yellow coloration, and acid nitrate of mercury produces no effect except when sulphuric acid is added, when the oil becomes of a clear citron-yellow. Bisulphide of calcium forms, with the oil, a granular canary-yellow soap, which subsequently loses its color.

## Correspondence.

Centennial of the United States Patent Laws.  
To the Editor of the Scientific American:

Noticing in your paper on the 12th ult. Mr. E. M. Shields' suggestion of celebrating in 1890 the centennial of the adoption and foundation of the United States patent office laws, I am pleased to see this important matter taken hold of by the SCIENTIFIC AMERICAN.

There is no doubt if all the inventors and men who have become rich through inventions would take an active interest in the matter in time. Why should we not have a celebration which would do credit to our country, and possibly be able to show the world that our country is the mother of invention?

DAVID G. WEEMS.

Baltimore, Md., March 16, 1887.

## Absorption through the Skin.

Ritter and Pfeiffer.—The method followed in their experiments was to rub well into the extensor surface of a healthy limb half an ounce of an ointment containing the substance under investigation, then to cover the spot with a protective bandage to prevent any possible absorption by the lungs, and after twenty-four hours to collect some urine and examine it for the presence of the drug. It was found that potassium iodide from a 10 per cent ointment passed into the urine in only one out of five cases, and this was after the ointment had been used for four days, when the skin had become irritated and its continuity practically destroyed by the prolonged action of the fatty acids derived from the decomposition of the lard. Sodium salicylate applied in the same way was never found, even in traces, in the urine; but salicylic acid invariably gave its characteristic color test with ferric chloride within a few hours after its application.

This behavior of salicylic acid is attributed to the property possessed by it of softening the epidermis and rendering it permeable, and the extent to which this takes place is shown by the fact that if the application of salicylic acid ointment be followed by one of potassium iodide ointment, the potassium iodide quickly passes into the organism and becomes detectable in the urine. When lard was replaced by lanolin, it was not found that the ointment manifested any superior penetrative power. Some other experiments made to test the capability of the skin to absorb substances sprayed on to it in watery solution gave, when precautions were taken to exclude the spray from the respiratory passages, only negative results.

## The Bids for Steel Armor Plates and Gun Forgings.

On March 22, four bids were opened by Secretary Whitney. These tenders referred to the supplying of "about 1,310 tons of steel gun forgings" and "about 4,500 tons of steel armor plates and appurtenances." The following is the abstract of the companies competing and of the terms agreed to:

| Name of Company.               | Armor plate.   | Gun steel.   |
|--------------------------------|----------------|--------------|
| Cambria Iron Company.....      | .....          | \$861,513.90 |
| Midvale Steel Company.....     | .....          | 1,397,240.00 |
| Bethlehem Iron Company.....    | \$3,610,707.50 | 902,330.79   |
| Cleveland Rolling Mill Co..... | 4,021,500.00   | .....        |

The Bethlehem Iron Co. agrees to provide the necessary plant to begin the delivery of the gun forgings within fifteen months, five months in advance of the requirements. It asks for the preference agreed to be given to the bidder who furnishes both classes of forgings, according to the naval department circular of August 21, 1886. The company, to prove its ability to carry out the contract, a condition exacted by the government, states that it has expended between \$300,000 and \$400,000 on its forging plant, and has on hand contracts amounting to \$500,000. It states that financial arrangements have been made for \$1,500,000 additional capital, and special engagements for the use of patents and for superintendence have been provided for with the largest European firms. The latter clause is said to refer to the great French works at Le Creusot. It is a source of the greatest gratification to find our American firms ready to undertake this work. It gives an additional proof of what always has been very patent, that the inventive and engineering genius of the country are able to cope with all of its needs and emergencies.

## A Paradise for Messenger Boys.

Intense excitement has been caused among the messenger boys employed by the Baltimore and Ohio Telegraph Company in Washington, D. C. A dozen Australian ponies for the use of the messenger boys recently arrived, and since then the boys of the city have gone wild over them. The ponies are small and very handsome, and as they stand saddled and bridled, with a rubber covering strapped on behind the saddle, they present a very neat and trim appearance, and, like the boys, they seem proud of their position. Since their arrival the B. & O. has been overrun with boys who want to be messengers, and are willing to work for nothing just to be able to ride one of the ponies.

## THE JENSEN ELECTRIC BELLS.

The special object of our visit to the show rooms of the Jensen Electric Bell and Signal Company, at No. 2 Gray's Inn Road, London, was to inspect a large consignment of bells on the Jensen system, for America, and which are designed for railway, telegraph, hotel, and private use. This system we now illustrate, and from our engravings it will be seen that the unsightly magnet box is dispensed with, and the hemispherical bell replaced by a bell of the church type, as at Fig. 1, inside of which is the electro magnet. This is a single solenoidal magnet of special construction, as seen at Fig. 2, and by it the armature is attracted by both poles simultaneously. By this means less than half the usual quantity of wire is required, thus reducing the external resistance of the circuit one half. Moreover, the armature, besides being magnetized by induction, as acted on in the ordinary method of making electric bells, is directly polarized by being in actual magnetic contact by the connection of the gimbals (which is in one piece with the armature) with the core iron of the magnet. It is thus induced to perform the largest amount of work with the smallest electromotive force. Instead of the armature and clapper being in a straight line attached to a rigid spring, which necessitates a considerable attractive power to primarily give it momentum, in the Jensen bell the armature and hammer are in the form of an inverted U, and, being perfectly balanced from the point of suspension, the lines of force from a comparatively small magnetic field suffice to set this improved form of armature into instant regular vibration.

By using a flexible break and make arrangement instead of the usual armature spring and set screw, a better result is attained, and the armature can be set nearer the poles of the magnet with sufficient traverse of the hammer. The reason why these bells require so little battery power to ring them is, first, because the armature and hammer are so perfectly balanced as to offer but little resistance; secondly, because the external resistance to the current is reduced; and, thirdly, because the best possible use is made of the electro-magnetic force at disposal. The bells are of elegant appearance, very sonorous, and can be fixed in any position, as exemplified by Figs. 3 and 4, the artistic mountings serving to show their symmetrical forms to advantage. Fig. 6 of our engravings is a sectional view of the bell and movement, showing the whole arrangement as already described.

Fig. 5 illustrates more clearly the insulator which acts as a collet for holding the movement securely in the bell, and at the same time effectually insulates it, so that by taking one end of the coil wire to the bell, as shown in our engravings, the bell, and consequently the bracket or hook it hangs on, forms one contact, and the terminal of the movement, as seen projecting through the top of bell, the other. For trembling bells, the other end of coil wire is fastened to the contact spring, for single strokes to the movement itself. An important feature is that by a simple arrangement the hours can be simultaneous-

ly struck on a number of bells, so that, if desired in a public building, large factory, an office, or for domestic use, the exact time can be synchronously rung out on as many bells as may be mounted in various places. Fig. 7 shows an arrangement for fixing the bell rigidly on board ship, or in any other circumstances where it is subject to oscillation.

The eye for suspending the bell on a hook will be seen to have been unscrewed and the bell placed in position for screwing on to the horizontal arm, or it can

panying engraving shows clearly how the knob was moulded, the method pursued being similar to that used in moulding intricate figures for casting in bronze. The sand was packed closely around one-half of the knob and its shank, and was then scraped entirely away from the top, while the rim was left covered for about one-third of its circumference and the shank for about one-half. The sand was then dusted, to prevent the next addition from adhering. Sand was then packed against about one-sixth of the rim at each side,

so that up to this point two-thirds of the rim had been covered. These two pieces were then dusted, when the entire top was moulded in one piece, as shown. The final operation was forming the cope or uppermost piece, which received the impress of the upper third of the rim and upper half of the shank. The five pieces comprising the mould were then separated, the knob removed, when the parts were re-assembled, baked, and the metal poured in through suitable gates in the usual way. The casting was sharp, clear, and a perfect copy of the original, to which it was decidedly superior, as it was made of one solid piece of metal. This specimen of moulding was done by Mr. James Kane at the brass foundry of Mr. James Reynolds, New Haven.

## On Sugar in the Blood.

A series of scientific and profound researches has been completed by Prof. Seegen, of Vienna, which has as its result the establishment of the fact that

the sugar formed by the liver is derived from albumen and fat.

A portion of the results obtained were published some time ago, and the general conclusions of the whole work are as follows:

1. That the blood passing from the liver contains an infinitely greater quantity of sugar than that entering the organ.
2. The newly formed sugar in the liver is wholly independent of saccharine food, as well as of the carbohydrates introduced with the food.
3. Even the liver glycogen is unconcerned in the production of sugar in the liver.
4. Albumen and fat are the materials out of which the liver forms sugar.

The fact that sugar is formed from fat is a new one, and is not in accord with the previously entertained chemical and physiological ideas. It appeared to the author, therefore, of much interest to experimentally

demonstrate the conversion of fat into sugar. This was accomplished by bringing together fatty bodies and blood with finely divided liver substance. The settlement of this question, that sugar is formed from fat by the liver, seems to point to that organ as the great laboratory in which the food is changed for the purposes of life, for the performance of work and the production of heat. It has a great practical significance, inasmuch as it teaches us the full worth of fat as material for food.—*Med. Review.*

THE shafts for the three U. S. Government vessels to be built by Messrs. Cramp in America are contracted for by the English steel makers, Messrs. Whitworth & Co.



IMPROVED ELECTRIC BELLS.

be screwed up to the vertical holder, seen to the left. Figs. 8 and 9 represent the Jensen indicators, which are exceedingly simple, there being no permanent magnet or other arrangement likely to get out of order. By a simple and inexpensive arrangement the bell can be fitted with a responding attachment, so that a person ringing to a servant can receive, by the servant pressing the button on his or her bell, an intimation that the summons has been heard and will be attended to. —Iron.

## MOULDING AN OLD FASHIONED KNOB.

A short time since, it became necessary to reproduce an old fashioned brass knob, which was so ornamented with raised figures as to prevent its being moulded in the ordinary way. The knob was made of hammered sheet metal, the top rim and back being in separate pieces, united by burnishing, and the shell thus formed being filled with plaster. The accom-



MOULDING AN OLD FASHIONED KNOB.

## PLAGUE OF LOCUSTS IN AUSTRALIA.

In the beginning of December last the Wallaloo and other districts of Victoria were visited by a plague of locusts, or rather grasshoppers. The amount of damage done was enormous; the farmers being driven to their wits' end as to what they should do with their stock until the summer is past, as grass as well as corn crops have disappeared before the advance of the clouds of insects. Hundreds of acres of crops have been eaten down to the ground, and hundreds of other acres partly destroyed. Reading & Sons in one day had 50 acres of crop, expected to yield 20 bushels to the acre, half destroyed, and 100 acres greatly damaged. In less than one week they had three selections of good grass leveled to the ground. S. Andrew had about 70 acres of wheat crop greatly damaged. During the time the reaper was cutting his oat crop the locusts ate more than half of it, and in a few days cleared his two selections of all grass. George Maunder had sixty acres of wheat badly injured, and his oat crop nearly eaten up. Two reapers could not cut down the crop fast enough to keep pace with the destruction of the pest. John Maunder had thirty acres of oats eaten up stalk and stump and his wheat crop was greatly injured. A. Main, T. Aldred, and several others have been great sufferers. The district looks like a barren waste.

On the Wallaloo Station there is not sufficient grass to feed the sheep. Fortunately, in some instances, the wheat crops are so far advanced that both stalk and grain were too hard for the pest to do much damage, any farther than eat off the low heads. Consequently, a few good crops are left standing, but these are few and far apart. Marnoo, Banyena, Cope Cope, Swanwater, Darkbonee, and other localities have suffered greatly. The locusts travel in companies about two miles wide, from two to three miles in length, and are from one to two inches thick upon the ground. They

are clearing everything before them at the rate of about three-quarters of a mile each day. Myriads of the insects have also visited the Great Western, where a number of young vines were destroyed. The old ones were not touched.—*Town and Country Journal.*

## THREE RELATED BREEDS OF DOGS.


Formerly, hunting exhibitions were held in the park of the Rosenborg Castle at Copenhagen, and in connection with the first of these there was a show of

Bernard. The finest of this class have been bred for the last thirty or forty years on the Broholm estate, from which they are called Broholm dogs. In the neighborhood of Copenhagen these dogs are seen everywhere. It is, in fact, a national breed, and although all specimens are not of equal value or size or of the same color, still there is a certain common type which is unmistakable. As the Kennel Club of Copenhagen has made a point of preserving and improving the breed, and has officially established the race marks, a greater uniformity will probably be reached. It is to be hoped that the past of the race and its relationship to the mastiff will be made subjects of investigation, as opinions on these points have heretofore been very divergent.

A repetition of the official enumeration of the marks of the breed would fill too much space, and therefore we will limit ourselves to mentioning a few of their characteristics. The Danish dog is of the same height and strength and, ordinarily, also of the same shape as the mastiff, but he is not so heavily built, and reminds one more of a powerful hunting dog. His head is not so broad, his ears are comparatively small, set high and lie smooth, his forehead is smooth (not wrinkled like that of the mastiff), the bridge of the nose is slightly arched, and the lips do not hang so low; his eye has a good natured and intelligent expression,


and shows no red at the corner. The color of the short, fine hair is reddish yellow (not ashy gray or dark brown, as is the mastiff's), and the muzzle and eyebrows are darker. Ordinarily, the Danish dog can run better than the pure mastiff, is not so heavy, is quicker and more active, and is highly commended as a companion and watchdog.

As is shown by the accompanying cut, the Danish or Broholm dog bears no resemblance to the German bulldog. The progenitors of the latter were carried from England and Ireland in great numbers in the



THE PLAGUE OF LOCUSTS IN AUSTRALIA.

dogs from all countries, which offered much that was new and interesting to lovers of these animals. In this way attention was called to the Danish dog, which does not resemble the German bulldog, but is undoubtedly a near relative of the English mastiff. It is difficult to decide whether there has been a cross here with the mastiff, or whether the Danish dog is simply a type of the heavy stag hound (*C. molossus*), from which, in the course of time, have come the English mastiff, the German bulldog, and, perhaps, also the progenitors of the present short haired St.



THREE RELATED BREEDS OF DOGS.

sixteenth century, and seventeenth century writers tell us that the race had increased to such an extent and the breed was kept so good that all importation of the dogs into Germany had ceased.

In the year 1876 there was a great international dog show at Hamburg, and on this occasion the breeders and connoisseurs present failed to establish a difference between the dogs to which the terms "Ulmer" and "Danish" had been applied in Germany; and at the shows held later in Berlin and Hannover, it was decided that there was no such difference, and that the animals to which these names had been given were really the German bulldog of three centuries back.

A fourth breed of dogs, the small but strongly built and plucky bulldog, is too well known to need any further description.—*Illustrirte Zeitung*.

#### Increasing Moisture in Rooms.

In a communication to the *Sanitary Engineer*, Mr. Henry R. Towne, president of the Yale Lock Manufacturing Company, at Stamford, Conn., says:

"As to my method of using steam for increasing the moisture in rooms, I will explain as follows:

"My house is heated by an indirect steam apparatus. Soon after building it I ascertained, by using a Mason's hygrometer, that in winter the air in the house was very dry, the humidity ranging as low as between 30 and 40 per cent of the dew point. Many sanitary authorities agree that 60 per cent humidity is desirable for health, and my personal experience seems to confirm this view. I thereupon endeavored, in various ways, to raise the percentage of humidity. I used evaporating pans and porous cups in front of the registers. Experimentally I tried wet cloths hanging from pans of water, which, by capillary action, gave considerable evaporation. All of these devices combined, however, failed to increase the moisture more than from 5 to 10 per cent.

"Finally, I made a small connection in one of the indirect steam coils, whereby I could admit a small jet of steam into the air box just under the coil. I at once found that this enabled me to raise the humidity to any desired point, the limit practically being that at which condensation on windows occurs. Since then I have had this arrangement applied to two of the coils on the main floor of my house, with the stems of the steam valves of the arrangement carried up from below, so the valves can be conveniently regulated from the room in which the moistened air is received. These valves are so adjusted as to allow a constant, but small, flow of steam into their respective air boxes. This is mingled with the inflowing air as it enters the heating coil, and is carried with it to the rooms above. The steam is delivered in each box through two one-fourth inch pipes, three inches apart. Under these hangs a small pan which catches the water of condensation as it drips from the ends of the steam pipes. A small overflow pipe carries off the water from these drip pans.

"With this arrangement I easily keep the moisture of my house at 50 to 60 per cent of saturation during winter. It is easy at any time to increase this percentage, but the result in cold weather is to cause rapid condensation on the windows, which is not desirable. A room heated to 70°, with the humidity at 60 per cent, is far more comfortable than one heated to 80°, with the humidity at 40 per cent, in my experience, as the former conditions are far more healthful. I am sure that the general adoption of my method of moistening the air in steam heated houses would be conducive to both health and comfort to all who live in them."

#### Asbestos Paper.


Mr. Ladewig has devised a process of manufacturing from asbestos fiber a pulp and a paper that resist the action of fire and water, that absorb no moisture, and the former of which (the pulp) may be used as a stuffing and for the joints of engines.

The process of manufacture consists in mixing about 25 per cent of asbestos fiber with about from 25 to 35 per cent of powdered sulphate of alumina. This mixture is moistened with an aqueous solution of chloride of zinc. The mixture is washed with water, and then treated with an aqueous solution of ammoniacal gas. The mixture is again washed, and then treated with a solution composed of 1 part of resin soap and 8 or 10 parts of water mixed with an equal bulk of sulphate of alumina, which should be as pure as possible. The mixture thus obtained should have a slightly pulpy consistency. Finally, there is added to it 35 per cent of powdered asbestos and 5 to 8 per cent of white barytes. This pulp is treated with water in an ordinary paper machine and worked just like paper pulp.

In order to manufacture from it a solid cardboard, proof against fire and water, and capable of serving as a roofing material for light structures, sheets of common cardboard, tarred or otherwise prepared, are covered with the pulp. The application is made in a paper machine, the pulp being allowed to flow over the cardboard. Among other uses, the asbestos paper has been recommended for the manufacture of cigarettes.—*L'Industrie Moderne*.

#### BOILER FEED REGULATOR.

Extended practical use has demonstrated that the machine herewith illustrated secures a uniform flow of water to the boiler, and holds the water in the boiler at whatever water line may be adopted. The tank in which the float rests is connected at the top with the steam space of the boiler, and at the bottom with the water space. Through the float is inserted a rod passing through holes in guides at the top and bottom of the tank. Actuated by this rod is a lever that operates a rod having a valve at both its upper and lower ends—the upper valve being in a pipe that conducts steam from the tank to the pump, while the lower valve is in the pipe conducting water from the pump to the tank. As the water lowers in boiler and tank, the float descends and operates the lever to open the valves. Steam is thus admitted to the pump, which forces water into the tank. As the water rises, the float ascends, and the valves are closed. Thus the pump is kept in motion sufficiently to supply the boiler, in which the water never rises too high or falls too low. The machine is absolutely free from packing, and has no bearing exceeding an eighth of an inch in length, so that friction is reduced to a minimum. The same and a uniform water line can be maintained in a battery of boilers, even if not provided with a mud drum and steam dome, but in such a case it would be necessary to provide each boiler with a machine. The regulator is so attached that it will not interfere with the pump connections in use, and, as shown in the engraving, is furnished with a water glass. A steam



WYMAN'S BOILER FEED REGULATOR.

gauge may also be attached. The simplicity of the device is evident, and its superiority is shown by the fact that its use has produced a saving in fuel, has enabled the engines to do more and better work, has prevented the burning of boilers, and has done away with leaking of the boilers.

This invention has been patented by Mr. Charles O. Wyman, Anoka, Minnesota.

#### Armor Plates.

In our consideration of the relative qualities of steel faced, or compound, and solid steel plates for the protection of belted, turreted, or barbette war ships, it is obvious, if we are to draw a conclusion from the consensus of nations and the awards of contracts by war offices, that the compound type possesses superior merits to the solid steel. Practically, the fact that over 70,000 tons of the former have been purchased and less than 20,000 tons of the latter, and that France has preferred the production of English metallurgists to that of Baron Schneider by a ratio, from 1880 to 1886 inclusive, of 14,957 tons in favor of the Sheffield armor as against 7,900 tons of the Creusot, would seem to be a conclusive argument for the compound type. We do not propose, however, to be actuated by simply commercial facts in our estimate of the qualities of the competitive systems. To adopt the precedents set by European nations in the character of war material, out of hand, would be not only inconsistent with American tradition, but antagonistic to the interests of domestic enterprise and production. The essays of England, France, and Germany in the direction of both guns and armor, it must be remembered, are yet but tentative.

The question of protection for our war ships is essentially one which we can decide for ourselves, and, when the type to be used shall be determined, can answer for ourselves. Though European contractors first put in actual shape the idea of an ironclad, the inspiration was our own, and the first trial of armor in warfare was in American waters.

The original armor for protected vessels was of wrought iron. At present the two types are of solid or homogeneous steel or of a steel face backed by wrought iron, the latter being known as compound. So far as we know, expert manufacturers in the United

States would recommend the latter type, and we refer to such producers of plate as Moorhead & Co., of Pittsburg, and others who have given the matter practical attention.

It is certainly most desirable that armor plate production should be organized in the United States; but the conditions prescribed by the Naval Ordnance Bureau are such as to deter sagacious and experienced manufacturers from even considering the enterprise. The policy of the department in selecting for the protection of our ironclads a material discredited by the great maritime powers, and condemned in its own country, is in our opinion not only inconsistent with an intelligent study of European results, but antagonistic to domestic industry. Past experience of the fairness of the Bureau has been sufficiently discouraging, without offering to producers the chance of a new investment under conditions known on their face to be impracticable.

Had there been a want of specific information as to the most recent trials of solid steel armor in Europe—a circumstance hardly possible in view of the acknowledged employment of officers of our Navy by its manufacturer—the obviously proper course to determine the relative merits of armor would have been to invite European producers to submit plates for trial in this country. It is within our knowledge that some time since, the Sheffield manufacturers of compound plate proposed such a trial to the Navy Department, offering to furnish at the proving ground, without a penny of cost to the department, a plate from 12 to 20 inches thick, 10 to 12 feet long by 6 to 8 wide, to be fired at in competition with solid steel, only conditioned upon the detail of the firing being made public. The proposition has not received the formality of an acknowledgment.—*Army and Navy Jour*.

#### Does Consciousness Continue after Decapitation?

On the 31st of January, Mr. Hayem read an interesting communication before the French Academy of Sciences upon the effect of transferring the blood of the horse into the head of animals that have just been decapitated. He finds, in the first place, that when the head of a dog is suddenly severed from the body, the eyes for some time execute motions of anxiety, the jaws forcibly open and close, the eyes afterward become fixed, the nostrils dilate, the labial commissures contract, and the tongue contracts to the back of the mouth. A few seconds later, a few respiratory efforts are remarked, and finally the head becomes inert. These phenomena, as a whole, never last more than two minutes.

If, as soon as the decapitation has been effected, the carotids are put in communication with the cubital artery of a horse, the vital manifestations are observed to last for half an hour. Finally, if the transfusion is not effected until the head has become inert, the various vital manifestations mentioned above reappear, but definitely cease at the end of a few minutes.

Mr. Hayem concludes that the extinction of will and sensation is very rapid, if not immediate. Conscious life may, nevertheless, be prolonged for a moment by transfusion, when the operation is performed immediately after decapitation; but in the case of the recall to life of an inert head, nothing but automatic motions, without any trace of will, or consciousness even, can be perceived.

Analogous experiments had already been performed by the learned physiologist Brown-Sequard, who came to the conclusion that the will returns to the head of a dog freshly severed from the body. Since then, this opinion has been submitted to no sort of verification. The experiments of Mr. Laborde with human heads that had been severed from the body for over an hour were performed under conditions where success was an impossibility.

THE following are the dates of the introduction of railways in the various countries from 1825 to 1860:

|                       |                  |
|-----------------------|------------------|
| England.....          | Sept. 27, 1825   |
| Austria.....          | Sept. 30, 1828   |
| France.....           | Oct. 1, 1828     |
| United States.....    | Dec. 28, 1829    |
| Belgium.....          | May 3, 1835      |
| Germany.....          | Dec. 7, 1835     |
| Ireland of Cuba.....  | In the year 1837 |
| Russia.....           | April 4, 1838    |
| Italy.....            | Sept., 1839      |
| Switzerland.....      | July 15, 1844    |
| Jamaica.....          | Nov. 21, 1845    |
| Spain.....            | Oct. 24, 1848    |
| Canada.....           | May, 1850        |
| Mexico.....           | In the year 1850 |
| Peru.....             | In the year 1850 |
| Sweden.....           | In the year 1851 |
| Chile.....            | Jan., 1852       |
| East Indies.....      | April 18, 1853   |
| Norway.....           | July, 1853       |
| Portugal.....         | In the year 1854 |
| Brazil.....           | April 30, 1854   |
| Victoria.....         | Sept. 14, 1854   |
| Colombia.....         | Jan. 28, 1855    |
| New South Wales.....  | Sept. 25, 1855   |
| Egypt.....            | Jan., 1856       |
| Middle Australia..... | April 21, 1856   |
| Natal.....            | June 20, 1860    |
| Turkey.....           | Oct. 4, 1860     |

## THE PANAMA CANAL WORKS.

The Panama Canal impresses the visitor as being one of the most gigantic engineering enterprises of modern times. Among the many difficulties to be overcome are those of taking the canal through the Chagres River some twenty times, through a hill several hundred feet high by means of a deep cutting, and through numerous swamps and beds of rock. When completed, it will be over fifty miles in length, twenty of which are now so far finished as to admit water, three miles having a depth of 25 ft. and the remaining seventeen a depth of 8 ft.


Among the sketches, the port of Colon, or Aspinwall, at once attracts attention, with its extensive wharves and sheds running out into the sea. Alongside these huge ships of all nations are so secured as to be ready "to slip" at short notice, in case of a gale coming on—a very necessary precaution, as not long ago seventeen large vessels were driven from their moorings and totally wrecked by the violence of a tropical storm. The sea there is never still, and to guard against its violence the entrance to the canal has been protected by a large breakwater run out into the sea, formed of concrete blocks, at the end of which is a large statue of Christopher Columbus, presented by the Empress Eugenie. At Mindi and other places are to be seen the bungalows of the engineers and workmen employed on the canal. These look beautifully clean and cool, and compare most favorably with the shanties of the negroes and Chinamen, who swarm about these parts.

The Cite de Lesseps—named after that illustrious Frenchman—is only a collection of huts, built of bamboos and any old refuse, and supported mostly on piles, often overhanging the muddy river, over swamps—in fact, anywhere. The canal cuts through the Chagres River there, and two large steam dredgers may be seen at work on the river discharging the dredged-up refuse far over the river's bank, through a long chute. Not only are there dredgers on the rivers, but on the land also, as at Las Cascadas, where a large locomotive dredger scoops up the earth and empties it into trucks the other side, by which it is taken away to form embankments, as at Bas Obispo.

Culebra presents a most animated scene—gangs of negroes, engines of novel construction in great numbers, all at work cutting through a hill some hundreds of feet high, through which the canal must pass. It is "man versus nature." With the exception of the engineers, negro labor only seems to be used, and as there is little sickness and good pay, the black man comes and works for a month or two, and then goes home and does nothing for the rest of the year. Wherever he is, he is always laughing, happy, and lazy. Our sketches and the above description are by Lieut. F. H. Boyer, R.N.—*London Graphic*.

## HOT AIR FURNACE.

Above the furnace proper, or fire box, are placed radiators, the whole being inclosed by walls of brick. The furnace is made heart-shaped in cross section, so that the fire box is wider at the top than at the bottom, thus causing the fuel to settle together upon the grate bars as it burns away, the result being a better combustion. The walls of the furnace are stiffened by a casting, bolted to the inner surface, so that they will



PAINE'S HOT AIR FURNACE.

not warp or sag if overheated. The grate bars are supported upon cross pieces, one at the center and one at the forward end of the furnace. Back of the grate bars is a perforated plate. The space below the grate and plate forms the ash pit. The interior of the furnace above the grate and plate is lined with corrugated and perforated fire bricks, which are held a short distance from the furnace walls, so as to form air spaces which communicate with the ash pit. A circulation of air is thus maintained between the fire box and walls of the furnace to protect the latter from intense heat.

Just above the furnace is placed a radiator, elliptical in cross section, and divided into three longitudinal compartments by two partitions, so inclined as to make the central compartment V-shaped. The partitions are of less length than the radiator, and as they abut the back of the radiator a passage is formed between their front ends and the front of the radiator. The rear ends of the side compartments are connected by flues with the furnace, so that the current caused by the draught will be forced through the side chambers and back

through the center one, and then through flue openings to the upper radiator, which is in all respects like the lower one, and the rear end of its center chamber is connected with the chimney flue. Connected to the front plates of the radiators are short pipes extending through the brickwork, and provided at their outer ends with caps, by removing which the interiors can be cleaned.

In each partition of the lower radiator is an opening, closed by damper plates operated by rods leading to the front of the furnace. These openings are in line with the flues, so that when the dampers are opened, the draught will pass directly from the furnace to the upper radiator. The lower radiator may thus be thrown out of action when desired. By setting the radiator partitions at opposite inclinations, the heat is confined near the surfaces at both sides and at the top, thereby causing the radiator to give off the maximum amount of heat. The intense heat produced at the front by the meeting currents is largely given off through the front plates of the radiators. This reverberatory action causes the smoke to be consumed and effects a better utilization of the fuel.


This invention has been patented by Mr. A. B. Paine, of Vermontville, Mich.

## Through Suez at Night.


It is quite a common thing for a big steamer to go through the Suez Canal at night. But what is, perhaps, not generally known is that the steamer itself, and not the Suez Canal Company, has to supply the requisite electric light apparatus for the nocturnal passage. What the company does is to prescribe the amount of illuminating power which the apparatus must possess. For instance, no steamer is allowed to start on a night transit that is not fitted with an "electric projector" which is capable of throwing a light for at least 1,200 meters ahead. And on the upper deck, too, there must be an electric lamp and shade powerful enough to light a circular area some 600 meters in circumference. Big steamers are beginning to carry this apparatus, but there is a company both at Port Said and Port Tewfik which lets out the necessary projectors and lamps on hire.

## Fidelity and Intelligence of the Dog.


The New York *Sun* says: "A Missouri farmer, driving home at night from St. Louis, dropped a coat and a bag of oats from his wagon without knowing it. His dog knew it, though, and lying down by them watched them for three days, despite all efforts to coax or drive him away. At the end of that time the farmer came back. He said that he had been wondering what had become of his coat, bag, and dog, and hearing of a dog acting strangely on the road, came to see if it was his."




ENTRANCE TO THE CANAL AT COLON, AND STATUE OF CHRISTOPHER COLUMBUS




LARGE LOCOMOTIVE DREDGER, LAS CASCADAS



CITE DE LESSEPS, WHERE THE CANAL FIRST CUTS INTO THE CHAGRES RIVER



THE PORT OF COLON, OR ASPINWALL



DEEP-CUTTING THROUGH THE MOUNTAINS, CULEBRA

VIEWS OF THE PANAMA CANAL WORKS FROM THE ISTHMUS RAILWAY.

## ENGINEERING INVENTIONS.

A muffler to prevent or lessen the disagreeable hissing sound caused by escaping steam has been patented by Mr. Thomas E. Hill, of Rahway, N. J. The invention covers a novel construction, combination and arrangement of parts, whereby the valves will permit the free escape of steam beyond the capacity of the boiler to generate it.

A metallic railway tie has been patented by Mr. Timothy Gleason, of Red Wing, Minn. It is cast or otherwise formed in trough shape, with flat bottom and vertical side pieces, and has cross pieces with a flange through which pass keys for supporting the fish plates, the upper surface of the bottom being formed with a crown, to strengthen the tie and prevent water from standing in it, with other novel features.

A railway crossing alarm has been patented by Mr. Sterling P. Van Nort, of Manchester, Mo. All the rails upon either side of each section of the track in connection with which the alarm is arranged are placed in electric communication by means whereby pedestrians, teamsters, etc., will be notified at the crossing of a highway and railroad of the approach of a train, and after its passage the alarm will be automatically stopped.

A boiler tube cleaner has been patented by Mr. Charles F. Bower, of Philadelphia, Pa. A spider with three arms is made integral with a nozzle shell, and a deflecting plate connected to the spider has an external head, while there are means for supplying steam to the nozzle, so that its inclined peripheral face will bear hard against the end edges of the bore of the tube, and steam passing in will strike against the entire inner face of the tube.

## AGRICULTURAL INVENTIONS.

A horse rake has been patented by Mr. James Dunkin, of Bridgeport, West Va. This invention covers a novel construction and arrangement of parts for a hay rake and carrier, intended to gather up the hay as it lies in the swath, load it into a carrier till it accumulates sufficiently, then carry it to place of storage and dump it.

A hay drag has been patented by Mr. William B. Null, of Evansville, Mo. It is provided on its main beam with runners, wheels, or supports, and has a supplemental runner, wheel, or support for the outer ends of the drag teeth, the construction being such that the drag can be readily transported from one place to another and may easily pass through gates.

## MISCELLANEOUS INVENTIONS.

A loose belt alarm has been patented by Mr. Jacob Paff, of Amboy, Minn. A friction wheel is journaled on the pulley, with its periphery extending beyond that of the pulley, on which an alarm is mounted to be operated by the friction wheel, in such way as to indicate audibly the slipping of the belt.

A thill coupling has been patented by Mr. E. Lauson Dunklee, of Wyalusing, Pa. The invention covers certain novel features, whereby a thill coupling is made practically noiseless, and is very easily adjusted and reliable, not expensive, without danger of disengagement, and has a neat appearance on the running gear of a vehicle.

A fruit jar has been patented by Mr. Robert E. King, of Warrenton, N. C. It has a main or fruit chamber and a supplemental or sirup chamber, the chambers being connected by a contracted channel or opening, so the fruit will be prevented from passing into the sirup chamber, while the sirup may pass into the fruit chamber.

A pipe connection has been patented by Messrs. William E. Jones and Harry Winniatt, of El Paso, Texas. The invention consists of two pipe heads fastened together and turning on a spring bolt, with a packing placed between the pipe heads to prevent leakage, to permit swinging several connected pipe sections at angles to each other.

A gas lamp has been patented by Mr. Gustave H. Ullmann, of Paris, France. This invention provides a cylindrical regenerating chamber, with air inlets, and a series of conical tubes, for the escape of the products of combustion, whereby the air will be mixed with the gas in a way designed to produce a white and brilliant light, with a minimum consumption of gas.

A clothes line has been patented by Mr. James Cavanagh, of New York City. Combined with two pulleys attached to a window frame and a pulley attached to a post is a line passed over all the pulleys, to form specified angles and an open loop connection, whereby two full length lines are made available, and any slack can be easily taken up.

A holdback iron for wagon tongues has been patented by Mr. Augustus Smith, of Laurin, Montana Ter. The invention covers a novel construction of a device for the ends of wagon tongues, which will prevent the neck yoke from escaping in case of accident to the harness, the yoke being easily removable when desired.

A vehicle wheel has been patented by Mr. William C. Hodnett, of Douglasville, Ga. It is composed of a tire made of two semicircular pieces of metal, spokes, and a central metal sectional hub, the semicircular sections of the tire being connected by splice plates and bolts, and the spokes being easily removable from their sockets, with other novel features.

An apparatus for drying malt has been patented by Mr. William S. Plummer, of Rochester, N. Y. It consists of a revolving drying floor, twenty to forty feet in diameter, suitably supported, with a series of movable or adjustable wickets, provisions for the forcible application of heated air and for the discharge of the malt, with other novel features.

A drag saw support and guide has been patented by Mr. John R. Van Winkle, of Aberdeen, Washington Ter. It is a roller support, with a main bar made in two jointed sections, a clamping

device at the joint, one section having dogs for attachment to a log and the other carrying a support and guide for the back of a saw blade, making a simple device for facilitating the undercutting of logs.

A cartridge extracting implement has been patented by Mr. Clarence R. Hart, of Sioux City, Iowa. It consists in a pair of jaws pivoted to a bowed spring and having a ratchet bar and catch for holding them in position, making a combination tool in which the jaws are adapted at one end to receive the flanged end of a cartridge and at the opposite end to act as tweezers for handling small objects.

A whiffletree coupling has been patented by Mr. Albert Hensser, of Taylor, Nevada. The invention covers certain novel features of construction and combination of parts for a coupling calculated to be strong, durable, cheap, and effective, and adapted also to be used in coupling bolsters to head blocks of vehicle running gear, and for other purposes where a strong, non-rocking, pivoted connection is required.

A thread guard for cap spinning and twisting machines has been patented by Mr. Leedham Binns, of Philadelphia, Pa. The guards are made of partly circular form at their backs, and peculiar shape at their front edges, where they are made to interlock with one another, with other novel features, the design being to prevent the several yarns from interfering or entangling with each other when being spun and twisted.

A machine for splicing wire hoops for barrels, etc., has been patented by Mr. James H. Bard, of Jackson, Tenn. This invention covers novel constructions and combinations of mechanism, in which the ends of the wire are made with a lock that consists of a bend and a coil of the extremities of the wire loosely fitting upon each side of the bend, with or without a space between the two coils for a spacing sleeve or wedge.

SCIENTIFIC AMERICAN  
BUILDING EDITION.

## APRIL NUMBER.

## TABLE OF CONTENTS.

1. Elegant Colored Plate of a Country House, costing \$1,800, designed for future enlargement, with two floor plans in colors, a large sheet of details of same, with 15 diagrams showing elevations and details of construction, with full specification of same, bills of estimate, etc.
2. Elegant Colored Plate of a Dwelling at Orange, N. J., costing \$5,000; with plans of floors in colors, sheet of details, elevations, etc., 12 figures, specification, etc.
3. The American School of Classical Studies at Athens. Half page engraving.
4. Page Drawing of a Country Dwelling in brick, costing \$5,000, with floor plans.
5. Perspective Drawing of St. Andrew's Church, Phenix, R. I., of moderate cost, with specification and floor plan.
6. Drawing of an Ornamental Business Front and City Residence.
7. Elevations and floor plans of a Cottage costing \$1,000.
8. An Ornamental Entrance Porch. Half page engraving.
9. Illustrations of the Mode of Filling Floors, Roofs, Side Walls, and Partitions.—Tests of Plumbing illustrated.—Hot Water Plumbing.—Illustrations of Fireplaces.
10. Perspective and floor plans for a Summer Hotel, two pages.
11. Two pages showing Stark's Design in perspective of proposed Monument to General Grant, New York, with plans.
12. Page drawing of the Great Nave, Cathedral of Mexico.
13. Drawing of the Pulpit, Church of the Holy Cross.
14. Design for an Ornamental Gate.
15. Two pages of Designs and Working Drawings of Ornamental Plaster Work, with directions for execution of same.
16. Perspective drawing of an English Country House.
17. Miscellaneous Contents: Floors and Ceilings, Ancient and Modern. By E. Powell Carr, Consulting Architect, New York; a valuable paper.—Useful Hints on House Building.—Shingles in Modern Architecture.—Diamond Point Nail Set.—Adjustable Wood Measuring Rack.—Redwood Logging.—Grano-Metallic Stone.—Black Birch.—Maple Flooring.—Water Tight Roofs.—Slate Roofs.—A Small Ice House, illustrated.—Mineral Wool as a filling for floors and walls, illustrated.—The use of mortar during frost.—Practical remarks on House Painting, exterior and interior.—Corrugated Iron Ornamental Ceilings, illustrated.—Together with a variety of other interesting articles and illustrations, too numerous to mention; and a Compendium of Manufacturers' Announcements, illustrated by upward of one hundred engravings.

The Scientific American Architects and Builders Edition is issued monthly. \$2.50 a year. Single copies, 25 cents. Forty large quarto pages, equal to about two hundred ordinary book pages: forming, practically, a large and splendid MAGAZINE OF ARCHITECTURE, richly adorned with elegant plates in colors and with fine engravings, illustrating the most interesting examples of Modern Architectural Construction and allied subjects.

The Fullness, Richness, Cheapness, and Convenience of this work have won for it the LARGEST CIRCULATION of any Architectural publication in the world. Sold by all newdealers.

MUNN & CO., PUBLISHERS,  
361 Broadway, New York.

## Business and Personal.

The charge for Insertion under this head is One Dollar a line for each insertion; about eight words to a line. Advertisements must be received at publication office as early as Thursday morning to appear in next issue.

The 9th edition (23d thousand) of "Trautwine" appeared in March, 1886. It was larger than its immediate predecessor by over 150 pages, the new index alone being more than twice as large as that of the 8th edition. Many of the old articles were modernized, and many new ones added. The present edition contains still further improvements.

Machine drawing and designing. A. K. Mansfield, Chicago.

Partner Wanted—A rare chance for a good mechanic on dies, tools, etc. Harness specialties from sheet brass. Unquestionable reference asked and given. Address "Paying Business," P. O. box 773, New York.

Want—My "Automatic Folding Seat" Tables for restaurants and beer gardens, manufactured on royalty or by contract. Address J. A. Reeder, Ramer, Tenn.

The Knowles Steam Pump Works, 113 Federal St., Boston, and 98 Liberty St., New York, have just issued a new catalogue, in which are many new and improved forms of Pumping Machinery of the single and duplex, steam and power type. This catalogue will be mailed free of charge on application.

Achromatic Telescope Lenses. F. W. Gardam, 36 Maiden Lane, N. Y.

Flea.—No screwing. T. C. Massey, Chicago, Ill.

Boiler Shop Tools Wanted—One steam riveter, 6 foot post; one plate planer, 18½ ft.; one punch, 36 inch reach, with spacing table; one set of 16 foot bending rolls; one horizontal flange punch. Above tools must be heavy and first class. May be new or second-hand. For Sale—One set of Niles pulley machinery, as good as new. Address Frick Company, Waynesboro, Pa. Give prices and full particulars.

For the latest improved diamond prospecting drills, address the M. C. Bullock Manfg. Co., 156 Lake St., Chicago, Ill.

Link Belting and Wheels. Link Belt M. Co., Chicago.

The Railroad Gazette, handsomely illustrated, published weekly, at 73 Broadway, New York. Specimen copies free. Send for catalogue of railroad books.

Protection for Watches.—Anti-magnetic shields—an absolute protection from all electric and magnetic influences. Can be applied to any watch. Experimental exhibition and explanation at "Anti-Magnetic Shield & Watch Case Co.," 18 John St., New York. F. S. Giles, Agt., or Giles Bro. & Co., Chicago, where full assortment of Anti-Magnetic Watches can be had. Send for full descriptive circular.

Woodworking Machinery of all kinds. The Bontel & Margedant Co., 116 Fourth St., Hamilton, O.

Concrete patents for sale. E. L. Ransome, S. F., Cal. Guild & Garrison's Steam Pump Works, Brooklyn, N. Y. Pumps for liquids, air, and gases. New catalogue now ready.

Presses & Dies. Ferracute Mach. Co., Bridgeton, N. J. Nickel Plating.—Sole manufacturers cast nickel anodes, pure nickel salts, polishing compositions, etc. \$100 "Little Wonder." A perfect Electro Plating Machine. Sole manufacturers of the new Dip Laquer Kristaline. Complete outfit for plating, etc. Hanson, Van Winkle & Co., Newark, N. J., and 92 and 94 Liberty St., New York.

Iron Planer, Lathe, Drill, and other machine tools of modern design. New Haven Mfg. Co., New Haven, Conn.

If an invention has not been patented in the United States for more than one year, it may still be patented in Canada. Cost for Canadian patent, \$40. Various other foreign patents may also be obtained. For instructions address Munn & Co., SCIENTIFIC AMERICAN patent agency, 361 Broadway, New York.

Curtis Pressure Regulator and Steam Trap. See p. 45. Iron and Steel Wire, Wire Rope, Wire Rope Tramways. Trenton Iron Company, Trenton, N. J.

If you have facilities for manufacturing sewing machines in quantities, write G. A. Annett, Bothwell, Canada. (Something valuable.)

Iron, Steel, and Copper Drop Forgings of every description. Billings & Spencer Co., Hartford, Conn.

Supplement Catalogue.—Persons in pursuit of information of any special engineering, mechanical, or scientific subject, can have catalogue of contents of the SCIENTIFIC AMERICAN SUPPLEMENT sent to them free. The SUPPLEMENT contains lengthy articles embracing the whole range of engineering, mechanics, and physical science. Address Munn & Co., Publishers, New York.

We are sole manufacturers of the Fibrous Asbestos Removable Pipe and Boiler Coverings. We make pure asbestos goods of all kinds. The Chalmers-Spence Co., 419 East 8th Street, New York.

New Portable & Stationary Centering Chucks for rapid centering. Price list free. Cushman Chuck Co., Hartford, Conn.

Steam Hammers, Improved Hydraulic Jacks, and Tube Expanders. R. Dudgeon, 24 Columbia St., New York.

60,000 Emerson's 1886 Book of superior saws, with Supplement, sent free to all Sawyers and Lumbermen. Address Emerson, Smith & Co., Limited, Beaver Falls, Pa., U. S. A.

Safety Elevators, steam and belt power; quick and smooth. D. Frisbie & Co., 112 Liberty St., New York.

"How to Keep Boilers Clean." Send your address for free 88 page book. Jas. C. Hotchkiss, 33 John St., N. Y.

The Holly Manufacturing Co., of Lockport, N. Y., will send their pamphlet, describing water works machinery, and containing reports of tests, on application.

Niagara Steam Pump. 30 years before the public. Always first premium. Adapted for all purposes. Norman Hubbard, Manufacturer, Brooklyn, N. Y.

Manufacturers' Advertising Bureau, 8 Broad St., N. Y. Benj. R. Western, Treas. Managers of advertising for firms. 20 years' experience. Best references.

Pattern makers' lathe. Back knife gauge lathe for turning chair stock. Rollstone Machine Co., Fitchburg, Mass.

Astronomical Telescopes, from 6" to largest size. Observatory Domes, all sizes. Warner & Swasey, Cleveland, O.

Split Pulleys at low prices, and of same strength and appearance as Whole Pulleys. Yocom & Son's Shafting Works, Drinker St., Philadelphia, Pa.

Send for catalogue of Scientific Books for sale by Munn & Co., 361 Broadway, N. Y. Free on application.

## Notes &amp; Queries

## HINTS TO CORRESPONDENTS.

Names and Address must accompany all letters, or no attention will be paid thereto. This is for our information, and not for publication. References to former articles or answers should give date of paper and page or number of question. Inquiries not answered in reasonable time should be repeated; correspondents will bear in mind that some answers require not a little research, and, though we endeavor to reply to all, either by letter or in this department, each must take his turn. Special Written Information on matters of personal rather than general interest cannot be expected without remuneration. Scientific American Supplements referred to may be had at the office. Price 10 cents each. Books referred to promptly supplied on receipt of price. Minerals sent for examination should be distinctly marked or labeled.

(1) L. L. & X. ask: 1. In the Atlantic cable, how is the circuit completed? A. By ground circuit, a condenser being used at one or both ends. 2. How is a break in the cable detected, and how located? A. If a fault in insulation, by determining the resistance and comparing it with that of the whole cable; if a breakage in the conducting wire, by determining the electrostatic capacity as compared with that of the entire cable. Either of these comparisons fixes the point.

(2) W. B. B. asks: 1. Can I electrify my body so that on shaking hands with some person, it will produce a shock if a circuit is formed with a chloride of silver battery, as described in SUPPLEMENT No. 137? A. By using an induction coil or a spark coil you can arrange a wire circuit so as to shock as described. 2. Could I work a set of telegraph instruments a half mile or less? How many will it take on each end? A. Five or six chloride of silver cells would work a half mile telegraph line. This number at each end would give an excellent working current.

(3) A. M. S. asks for the process of liquefying nitrous oxide gas and oxygen gas so as to compress 100 gallons into cylinders, as it is put up for dental use and oxygen treatment. A. Nitrous oxide is liquefied by pressure. It is pumped into cylinders until the pressure reaches about fifty atmospheres, when it liquefies and continues to do so as long as it is pumped in. Oxygen cannot be liquefied except by special processes, such as Clalletet's or Pictet's. It is used in the oxygen treatment from cylinders into which it is pumped under heavy pressure, but in which it never leaves the gaseous form. The apparatus can be bought from dealers in scientific apparatus.

(4) E. McD. asks: How can I prepare a liquid such as is used in grenades, etc., for extinguishing fires, to be used with a hand force pump? A. The liquid consists of sodium chloride, ammonium chloride, and hydrochloric acid dissolved in water with the addition of potassium carbonate, and subsequently sodium bicarbonate, and last of all a little free crystallized tartaric acid. See the answer given to query 7 in SCIENTIFIC AMERICAN for February 7, 1885, also recipes in Spont's "Workshop Receipts," second series, which we can send you for \$2.00, post paid.

(5) F. A. B. writes: In hardening our goods, we have been using iron pots to hold the lead in which we bring the articles to a hardening heat. The result is that the iron pots will only stand the necessarily intense heat for a few days, then give way in the bottom, and the lead runs into the fire. Can you tell us of any material that will be durable, of which to have our pots made? Say size 12 inches by 8 inches by 4 inches. Would a crucible work well, and if so, how could it be best supported in the fire? A. A plum-bago crucible resting upon a fire brick will be durable. We recommend an oval or round shape, with slightly rounded bottom. Set these on three fire bricks standing on end, which will give support and prevent too strong fire on the bottom.

(6) W. J. D. asks: What is the difference between a tornado and a cyclone, and from what authorities? A. The word tornado is used to indicate any wind of extreme violence, from 90 to 120 miles an hour. The word cyclone is properly used to denote whirlwinds, which in the northern hemisphere rotate in direction opposed to that of the hands of a watch. The Cyclopedias, Haswell, and Ganot all speak of the subject.

(7) G. H. McC. asks: 1. What is the copper colored paint used to paint the bottoms and water lines of fresh water yachts and vessels? A. Essentially it is oxide of copper with tar and a solvent. The composition is a secret. 2. Will it get soft under water? A. No. 3. Is there any way to prevent weeds and moss from growing on the bottoms of small yachts? A. Use verdigris or approved copper paint, or coat with bronze powder and copal varnish.

(8) J. P. asks: Can a locomotive start a greater weight than itself, on the track, providing there is no play between the couplings? A. The power of a locomotive is largely in excess of the requirement of starting a given load, of many times its own weight, by a dead pull. The play of the couplings only becomes of value in excessively heavy and long trains. The engine's hold on the rails depends on sliding friction. The resistance of the cars outside of inertia depends principally on rolling friction. The latter is far less for a given weight than is the first.

(9) G. B. T. asks why, in listening to an echo, one can only hear the last part of a sentence. A. The last words of the speaker drown the echo of the first words, which is returning while one is speaking. Dancell's Physics treats the kinetic theory very thoroughly. We mail it for \$4.

(10) S. S. S. asks (to decide a bet) the proper door to open and the door to shut, after lighting the fire, to insure proper draught and combustion, in starting a fire in the furnace of a regular heating boiler. A. The question is one which cannot be fully

answered by simply saying one or the other, or by a yes or no, as is sometimes the case in a question on which a wager is pending. Such disputes usually arise from a misunderstanding, or a difference in statement of the terms, rather than in a variance of opinion as to the actual question at issue. Fires are started both ways, with the ash pit door or with the furnace door open, according as the fire is laid, the attention to be given it and the time. Ordinarily a fire under a boiler should, if possible, be lighted on top of the kindling material, so that the first combustion shall be perfect to start the draught. The top door should be open that the fresh air may reach the flame and prevent dense smoke. When the kindling wood is well on fire, open the lower door a little way to clear the smoke from the ash pit and establish a draught through the grating. Then put on coal and shut the upper door, opening the lower door enough to keep the fire bright. With a little management in this way a fire may be started under a house heating boiler without filling the house with smoke. In starting a fire under the grate, with the ash pit door open, the fuel must be more carefully laid to insure a draught to start with, and the initial progress is then frequently accompanied with puffs of smoke.

(11) H. R. F. asks what chemicals, if there are any, will separate tannic acid from gelatin, also what will dissolve common tanned leather? A. It is one of the first illustrations frequently employed in the study of chemistry, that tannic acid and gelatin make a chemical, and not a mechanical, compound, and become an insoluble one. The gelatin and tannic acid cannot be recovered back from such compound; nor can tannic acid, fibrine, and gelatin, of which tanned leather is made, be ever brought back to their original condition after being once made into leather. There are some adherents in Germany of a theory that tanning is a mechanical and not a chemical combination, but it has never been proved. A great difficulty with the subject lies in the fact that there is much difference in the action and power of combination of the tannins obtained from different substances, for reasons which are not understood; the tannin from gambier, valonia, sumac, etc., can be washed out of a skin to a certain extent in a way which cannot be accomplished when the tanning is done with oak or hemlock bark.

(12) R. G. P. asks how many Grenet batteries it will take to run a boat 20 ft. long by 4 ft. 4 in. beam, and 21 in. deep, how many miles an hour. A. About 3,000 ordinary sized Grenet cells would be required to develop a speed of 6 to 7 miles an hour. If you want to use batteries, you need special large sized low-resistance cells, and of these far fewer would be needed, say 250 cells.

(13) T. E. writes: We have a barge sunken; her decks are tight, but 24 feet below the surface of the river. In pumping her out, please tell me which will require least power—to pump the water above the decks, and discharge it 23 feet below the surface, or to pump it above the surface of the river? A. The same power will be required, assuming the water to be discharged exactly at the surface level in the second case supposed. If discharged above the surface, the extra height represents extra power.

(14) L. L. asks how frozen glue is made, such as is used by leather manufacturers. A. Frozen glue is what its name denotes. The glue while gelatinous is sliced, placed on nets and allowed to freeze by natural cold. Of course the process can only be conducted in cold weather. The product is porous and much more bulky than hard glue, but is a better article, as it dissolves more easily. It sells largely in New England, where it is preferred by buyers to the hard glue.

(15) J. H. P. asks: 1. The kind of iron and the mixture for making malleable iron. A. No. 5 and 6 iron mixed, or scrap and No. 6. 2. The best kind of scale to put in the annealing cans, and how long should it take to anneal a round piece, say one-half inch thick. A. Forge scales or pulverized hematite, anneal 4 to 6 days at red heat. See SCIENTIFIC AMERICAN SUPPLEMENT, No. 399, "Malleable Iron Castings."

(16) M. E. P., Kentucky, asks: Is there any means of patching or resilvering mirrors, which I could do at home? A. Clean the bare portion of the glass by rubbing it gently with fine cotton, taking care to remove any trace of dust or grease. If this cleaning be not done very carefully, defects will appear around the place repaired. With the point of your knife cut upon the back of another looking-glass around a portion of the silvering of the required form, but a little larger. Upon it place a small drop of mercury; a drop the size of a pin's head will be sufficient for a surface equal to the size of the nail. The mercury spreads immediately, penetrates the amalgam to where it was cut off with the knife, and the required piece may now be lifted and removed to the place to be repaired. This is the most difficult part of the operation. Then press lightly the renewed portion with cotton; it hardens almost immediately, and the glass presents the same appearance as a new one.

(17) G. H. W., Waterville, Me., asks: 1. How can I remove tincture of iron stain from a cotton fabric, and indelible ink stain from linen? A. Use dilute hydrochloric acid in order to remove the iron stain, and javelle water or some of the hypochlorites for the ink stain. See "Table for Removal of Stains and Grease Spots," in SCIENTIFIC AMERICAN SUPPLEMENT, No. 158.

(18) W. G. McC., Lake Forest, Ill., asks how to make a white ink. A. For writing on black or dark paper, use the finest or lightest zinc or white lead in a weak solution of gum arabic or dextrine. For writing on blue paper, tinted with ultramarine, use a solution of oxalic acid.

(19) A. M., Lowell, Mass., wants the manner or process of curling feathers worn on ladies' bonnets. A. When the curl has come out by washing the feather or getting it damp, place a hot flat iron so that you can hold the feather just above it while curling. Take a bone or silver knife, and draw the fibers of the feather between the thumb and the

dull edge of the knife, taking not more than three fibers at a time, beginning at the point of the feather and curling one half the other way. The hot iron makes the curl more durable.

(20) A. C. M. asks: Will two cells of Grenet battery (size of zincs  $2\frac{1}{2}$  by  $4\frac{1}{4}$  in.) have sufficient power to run a one candle power electric lamp? A. Four cells would be necessary to give satisfactory results.

### TO INVENTORS.

An experience of forty years, and the preparation of more than one hundred thousand applications for patents at home and abroad, enable us to understand the laws and practice on both continents, and to possess unequalled facilities for procuring patents everywhere. A synopsis of the patent laws of the United States and all foreign countries may be had on application, and persons contemplating the securing of patents, either at home or abroad, are invited to write to this office for prices, which are low, in accordance with the times and our extensive facilities for conducting the business. Address MUNN & CO., office SCIENTIFIC AMERICAN, 361 Broadway, New York.

## INDEX OF INVENTIONS

For which Letters Patent of the United States were Granted,

March 15, 1887,

AND EACH BEARING THAT DATE.

[See note at end of list about copies of these patents.]

Adjustable table, G. Zaccaro..... 359,340  
Alarm. See Bell alarm. Druggist alarm. Railway crossing alarm..... 359,338  
Ambulance spring, Hauser, Jr., & Ritzler..... 359,338  
Atomizer, M. F. Sallade..... 359,338  
Auger bits, die for making, W. C. Johnson..... 359,338  
Automatic gate, J. C. Rock..... 359,404  
Awning for windows or doors, Thalheimer & Kautner..... 359,338  
Axle and wheel, J. Pettinger..... 359,405  
Ball, detonating, S. Armstrong..... 359,400  
Band cutter and feeder, O. Anderson..... 359,487  
Barium binoxide, making, A. Brin..... 359,423  
Basins, device for preventing clogging of catch, L. E. Dingle..... 359,344  
Baskets, handle for peach, S. C. Case..... 359,341  
Bell, electric, F. B. Wood..... 359,309  
Bell alarm, loose, J. Paff..... 359,403  
Bench. See Wash bench.  
Bicycle, B. Kelsey..... 359,448  
Bicycle brake, Hazen & Hildreth..... 359,536  
Bin. See Flour and meal bin.  
Blackening on ladies' shoes, device for applying, H. M. Wirt..... 359,527  
Board. See Stove board.  
Boat. See Torpedo boat.  
Boat indicator, A. Leith..... 359,511  
Bogs, apparatus for cutting, C. E. Patterson..... 359,541  
Boiler. See Steam boiler.  
Boiler cleaner, A. De Camp..... 359,501  
Boiler tube cleaner, C. F. Bower..... 359,388  
Book holder, A. Dom..... 359,245  
Books, making indexed, E. C. M. Rand..... 359,409  
Boring machine, C. McNeil..... 359,370  
Boring tool, metal, G. W. Tower..... 359,336  
Bottle attachment, J. F. H. Sugg..... 359,412  
Bottle stopper, Woodham & Ockenden..... 359,373  
Bowling alley, Reisky & Wolff..... 359,542  
Box. See Fano box. Letter box. Musical box. Paper box. Wagon box.  
Box or tub fastener, J. H. Burt..... 359,344  
Brake. See Bicycle brake. Car brake.  
Breastpins, pin tongue for, Hauser & Haberl..... 359,330  
Brick mould sanding machine, H. & G. Martin..... 359,367  
Brush, H. E. Fowler..... 359,250  
Bucket, minnow, C. E. Bateman..... 359,311  
Buckle, back band, Garrett & Sanford..... 359,254  
Bustle, H. O. Canfield..... 359,240  
Bustle, D. Werts..... 359,308  
Caliper gauge, J. Tickell..... 359,295  
Can. See Milk can.  
Car brake and starter, E. Giroux..... 359,386  
Car coupling, J. F. & W. J. Rowley..... 359,377  
Car coupling, S. B. Fyler..... 359,253  
Car coupling, S. Wells..... 359,481  
Car door, J. W. Peters..... 359,281  
Car seat, H. S. Hale..... 359,354  
Car spring, G. W. Morris..... 359,359  
Car starter and brake, Mahan & Hendrix..... 359,295  
Car, stock, G. D. Burton..... 359,346  
Car, wheel, W. W. Snow..... 359,332  
Cars, fare box for street, Wherry & Turman..... 359,482  
Carburetor, F. Well..... 359,365  
Carding engines, bend for, G. & E. Ashworth..... 359,329  
Case. See Document case.  
Caster pod, C. V. Plunkharp..... 359,362  
Casting ingots, bars, etc., apparatus for, F. H. Daniels..... 359,349  
Casting rivets, mould for, J. Whitley..... 359,484  
Castings, mould for the production of metallic, J. Whitley..... 359,483  
Chain, E. Vielle..... 359,413  
Cigar bunching machine, F. C. Smaistig..... 359,478  
Cigar tip protector, P. Miah..... 359,356  
Clamp for moulder's flasks, D. Frawley..... 359,251  
Clasp, W. E. Moore..... 359,430  
Cleaner. See Boiler cleaner. Boiler tube cleaner.  
Cleat or rope fastener, F. Kruegermann..... 359,538  
Cloth cutting machine, P. Howe..... 359,370  
Clothes drying frame, R. Orr..... 359,275  
Clothes line, J. Cavanaugh..... 359,427  
Coin counter with automatic locking device, J. L. Townsley..... 359,328  
Coloring matter, manufacture of red, A. Romer..... 359,370  
Cooler. See Milk cooler.  
Copying apparatus for manuscript, B. J. Wallace..... 359,282  
Cornstalk cutter, W. Walker..... 359,300  
Cotton or hay press, C. D. Neeb..... 359,515  
Coupling. See Car coupling. Pipe coupling. Thill coupling. Tire coupling.  
Crank wheels, device for applying foot power to, J. C. Clark..... 359,259  
Creamer or milk pitcher, H. Wettstein..... 359,304  
Crushing and grinding mill, J. F. Winchell..... 359,288  
Cuff holder, E. Zoller..... 359,228  
Cultivator, J. Chalfant..... 359,242  
Cultivator, C. S. Guilkey..... 359,285

Cultivator, A. J. Nelson..... 359,400  
Cultivator, J. W. Robinson..... 359,285  
Cultivator attachment, H. C. Pratt..... 359,518  
Cup. See Oil cup.  
Cutter. See Band cutter. Cornstalk cutter.  
Desk, L. Smith..... 359,474  
Desks, ink well for school, M. S. Smith..... 359,383  
Document case or record cabinet, etc., J. C. Lang..... 359,451  
Door plate, knocker, and letter receiver, combined, W. A. Moore..... 359,426  
Dough, machine for sheeting, J. H. Mitchell..... 359,273  
Drill. See Seed drill.  
Druggist alarm, M. Toulmin..... 359,361  
Dumb waiter, E. M. Foster..... 359,427  
Ear muff, A. L. Britton..... 359,425  
Eggs, device for turning, S. H. Raymond..... 359,327  
Electric circuits, apparatus for testing, A. D. Wheeler..... 359,338  
Electric motor, E. P. Clark..... 359,429  
Electrode and shield, canter, D. H. Goodwillie..... 359,500  
Elevator. See Sucker rod elevator.  
Engine. See Wind engine.  
Explosives, primer for igniting, L. Bagger..... 359,401  
Fabrics, machine for plicating and packaging, P. H. Watson..... 359,584  
Fare box, J. S. Capers..... 359,346  
Faucet or cock, W. B. England..... 359,346  
Feeder and sifter, combined, J. T. Burkett..... 359,406  
Fence, H. Rong..... 359,520  
Fence, C. N. Town..... 359,297  
Fence post, D. Bowen..... 359,589  
Fence post, H. Datesman..... 359,434  
Fence post, J. E. Hunt..... 359,257  
Fence wire strainer, W. Orr..... 359,464  
Fender. See Vehicle fender.  
File holder and rack, P. S. Dusenbury..... 359,560  
Filter, water, A. J. Kaiser..... 359,258  
Filtering apparatus, D. Fitz Gerald..... 359,349  
Firearm, A. Chucho..... 359,428  
Fire escape, Wilcox & Merrill..... 359,536  
Fire kindler, R. Miller..... 359,272  
Flour and meal bin, portable, T. J. Cox..... 359,347  
Frame. See Clothes drying frame.  
Frame for pictures, mirrors, etc., F. Damos..... 359,316  
Fruit jar, R. E. King..... 359,449  
Gauge. See Caliper gauge. Surface and marking gauge.  
Game register, E. Griswold..... 359,562  
Garden rake, G. W. Hertzel..... 359,355  
Garment supporter, R. H. Sink..... 359,365  
Garment supporter, C. Sisson..... 359,365  
Garments, elastic gore or section for, J. Kendrick..... 359,336  
Gas engines, electric igniter for, N. C. Bassett..... 359,552  
Gas, incandescent, C. A. Von Welsbach..... 359,524  
Gas, manufacture of, A. Taylor..... 359,335  
Gate. See Automatic gate.  
Gate, M. B. Mills..... 359,398  
Generator. See Steam generator.  
Glass beveling machine, T. F. Gilroy..... 359,439  
Glass lamps, manufacture of, P. Arbogast..... 359,489  
Glass mould, M. L. Blackburn..... 359,553  
Glass, machine for cutting, D. Jarvis..... 359,391  
Governor, engine, E. Verstraete..... 359,259  
Graduating machine, G. F. Ballou..... 359,578  
Grain binder, Miller & Ellinwood..... 359,271  
Grain binder conveyor, W. P. Essig..... 359,347  
Grain binding machines, grain adjusting device for, H. J. Case..... 359,426  
Grain separator, N. Hollinger..... 359,569  
Grain separator and grader, E. A. Mueller..... 359,514  
Grinding the screws in tack dies, machine for, A. E. Conyers..... 359,583  
Gunpowder, E. Schultze..... 359,289  
Hair springs to collars, fastening, E. Hunziker..... 359,390  
Hame fastener, L. W. & H. L. Bowman..... 359,494  
Hame fastener, H. H. Brandes..... 359,422  
Handle. See Tool handle.  
Harrow, smoother, and seeder, combined, J. M. Poore..... 359,363  
Harrow, spring tooth, W. S. Lawrence..... 359,539  
Harrow, wheel, J. A. Van Tassel..... 359,478  
Harrow, wheel, W. Wilkes..... 359,339  
Harvester, cotton, O. T. Buga..... 359,554  
Harvester cutting apparatus, T. S. Houser..... 359,256  
Hay drag, W. B. Null..... 359,402  
Heating apparatus for buildings, E. N. Gates..... 359,561  
Hinge for mirrors, friction, J. F. Buzzell..... 359,555  
Hoisting apparatus for mines, T. Poore..... 359,517  
Hoisting jack, D. B. Scott..... 359,405  
Holdback iron for wagon tongues, A. Smith..... 359,367  
Holder. See Book holder. Cuff holder. File holder. Label holder. Rein holder. Spool holder.  
Hook. See Snap hook. Suspension hook.  
Horse power, J. A. Spencer..... 359,475  
Horse power, lat iron for, H. Moody..... 359,399  
Horse rake, J. Dunkin..... 359,534  
Hub attaching device, J. Kent..... 359,262  
Hydraulic elevator valves, operating mechanism for, N. C. Bassett..... 359,551  
Hydrocarbon, process of and apparatus for refining, E. D. Kendall..... 359,257  
Indicator. See Boat indicator. Station indicator.  
Ingot, compound, E. Wheeler..... 359,337  
Iron. See Holdback iron.  
Iron beams, fastening objects to, C. B. Art..... 359,330  
Iron, pile for skelp, W. G. Howell..... 359,508  
Jack. See Hoisting jack. Lifting jack.  
Jar. See Fruit jar.  
Joint. See Rail joint.  
Knife. See Roller knife.  
Knitting machine, circular, J. Byfield..... 359,586  
Knitting machines, cam cylinder for, J. B. Paxton..... 359,235  
Label holder, J. E. Lathrop..... 359,265  
Lace fastening, T. T. Danforth..... 359,438  
Lamp, double reservoir, C. H. Denison..... 359,502  
Lamp, electric, C. Seal..... 359,328  
Lamp, gas, G. H. Ulmann..... 359,370  
Lamp or gas heating attachment, C. B. White..... 359,415  
Lamp, overhead or ceiling, A. M. Silber..... 359,364  
Lamps, adjustable overflow device for, O. J. Heyne..... 359,567  
Lamps, overflow device for, O. J. Heyne..... 359,566  
Lantern, L. F. Betts..... 359,341  
Lathe for turning balls, wheels, etc., G. F. Ballou..... 359,380  
Lathe, slide, G. F. Ballou..... 359,381  
Lathe, drilling fixture for, G. F. Ballou..... 359,375  
Lathe, gear cutting device for, G. F. Ballou..... 359,377  
Lathe, work clamp for slide, G. F. Ballou..... 359,379  
Lathe, work holder for, G. F. Ballou..... 359,352  
Lead, manufacture of white, E. V. Gardner..... 359,352  
Letter box, T. S. Scoville..... 359,548  
Level, spirit, W. C. Thatcher..... 359,580  
Lifting jack, P. J. Abbott..... 359,486  
Lifting jack, A. A. Strom..... 359,411  
Lock. See Nut lock. Permutation lock. Seal lock. Time lock.  
Lock, M. B. Otis..... 359,276  
Loom, circular, G. Wasserman..... 359,414  
Loom shuttle, B. Soaries..... 359,548, 359,546

Lubricant, J. B. C. Barbanson..... 359,418  
Lumber, etc., device for binding together, J. T. Barber (r)..... 10,817  
Malt drying apparatus, W. S. Plummer..... 359,284  
Measuring fabrics and printing the measures thereon, machine for, A. H. Sutton..... 359,393  
Measuring textile fabrics, etc., machine for, Sutton & Watson..... 359,579  
Measuring textile fabrics, etc., machine for, P. H. Watson..... 359,583  
Metal, mechanism for forming ingots, bars, rods, etc., from fluid, F. H. Daniels..... 359,348  
Metals, uniting, F. A. Godfrey..... 359,310  
Metallic table for machine tools, F. W. Taylor..... 359,399  
Milk can, E. Pabst..... 359,401  
Milk cooler, H. Kennen..... 359,261  
Mill. See Crushing and grinding mill.  
Mining machine, B. A. Lutz (r)..... 10,819  
Mould. See Glass mould.  
Mole trap, J. H. Marlin..... 359,654  
Mothproofing hair, J. & J. Ruch, Jr..... 359,287  
Motor. See Electric motor. Pressure motor.  
Mower, lawn, G. M. Williams..... 359,530  
Mowing machine attachment, W. B. Fox..... 359,351  
Muffler, T. E. Hill..... 359,390  
Music leaf turner, J. Herron..... 359,396  
Musical box, E. Parr..... 359,376  
Musical instrument, automatic, E. Parr..... 359,379  
Nail machine, D. C. Stov..... 359,583  
Nail machine, wire, H. B. Happe..... 359,564  
Nut lock, Dambach & Hannan..... 359,265  
Oar, J. Wright..... 359,273  
Oil cup, E. Lunkenheimer (r)..... 10,819  
Ordinates, apparatus for placing and obtaining the mean value of, J. G. Claud-Mantle..... 359,400  
Ore and rock crushing and pulverizing machine, H. Bradford..... 359,495  
Oxygen from air, apparatus for obtaining, L. Q. & A. Brin..... 359,434  
Pad. See Shoulder pad.  
Paper and process for the manufacture thereof, felt, F. Beck..... 359,531  
Paper, etc., apparatus for drying, G. L. Jaeger..... 359,446  
Paper box, C. W. Elliott..... 359,435  
Paper calendaring machine, P. R. Thom..... 359,394  
Paper pulp screen, Russell & Cragin..... 359,543, 359,544  
Pasting machine, J. R. Watson..... 359,301  
Permutation lock, E. O. Daniels..... 359,260  
Piano action, T. Cahill..... 359,267  
Pipe connection, Jones & Winniatt..... 359,394  
Pipe coupling, W. G. Davis..... 359,390  
Pipe moulding apparatus, McNeal & Stinerack..... 359,389  
Play with rotating gig, G. Fischer..... 359,317  
Plow, E. H. Inzer..... 359,321  
Plow, T. Pate..... 359,466  
Plow, gang, F. M. Hinchman..... 359,355  
Pneumatic dispatch tube, electrical, J. F. McLaughlin..... 359,540  
Pneumatic dispatch tube system, carrier for electro, J. F. McLaughlin..... 359,456  
Pocket, detachable watch, C. A. Burbank..... 359,343  
Post. See Fence post.  
Pot. See Tea or coffee pot.  
Power. See Horse power.  
Press. See Cotton or hay press.  
Press and seaming machine, combined, H. Patterson..... 359,390  
Presser foot and attachment holder, combined, J. P. Lavigne..... 359,453  
Pressure motor, fluid, G. Westinghouse, Jr..... 359,303  
Pressure regulator for water supply mains, D. C. Cregier..... 359,315  
Printing machine, oscillating cylinder, J. T. Hawkins..... 359,443  
Printing machine, plate, S. F. Millard..... 359,313  
Propeller shaft, stern bearing for, J. J. Townsend..... 359,398  
Protector. See Cigar tip protector. Sleeve protector.  
Pump, D. J. Nysewander..... 359,516  
Pump, force, R. Bean..... 359,419  
Push button and thermostat, combined, Koffer & McDowell..... 359,360  
Rail joint, J. W. Storrs..... 359,521  
Railway crossing alarm, S. P. Van Nort..... 359,371  
Railway signal, M. W. Long..... 359,512  
Railway tie, metallic, T. Gleason..... 359,440  
Railway track and truck, W. F. Goodwin..... 359,507  
Railways, conduit for traction rope or endless cable, Z. P. Boyer..... 359,421  
Railways, crossing for cable, H. H. Lynch..... 359,396  
Railways, etc., bridge for elevated, G. H. Pegram..... 359,467  
Rake. See Garden rake. Horse rake.  
Register. See Game register. Telephone register.  
Regulator. See Pressure regulator.  
Rein holder, D. Goff..... 359,555  
Rim turner, G. A. Kollenberg..... 359,263  
Rock drilling machine, combined hand and engine power, J. C. Stevens..... 359,578  
Roller knife, W. Weber..... 359,480  
Roofs of buildings, protecting, G. F. Gavitt..... 359,318  
Rug, E. H. Eisenhart..... 359,504  
Safe, bottle, D. Getleson..... 359,438  
Sash fastener, F. W. Mix..... 359,274  
Saw and planer, combined, H. F. Burkhardt..... 359,497  
Sawmill set works, A. B. Landis..... 359,264  
Scraper, road, F. W. Hubbard..... 359,537  
Screen. See Paper pulp screen.  
Seal lock, T. F. Anderson..... 359,488  
Seal lock, J. A. Kirby..... 359,480  
Seat. See Car seat.  
Secondary batteries or accumulators, positive pole plate for, Farbak & Schenck..... 359,248  
Seed drill, F. Heyner..... 359,470  
Separator. See Grain separator.  
Separator, W. L. Card..... 359,496  
Sewing machine, J. Keith..... 359,573  
Sewing machine tension device, B. C. Bedell..... 359,430  
Sewing machines, binding attachment for, C. T. Jones..... 359,572  
Sewing machines, welt guide for shoe, E. F. Arnold..... 359,280  
Sewing with wire, machine for, L. Hall..... 359,563  
Shafts, manufacture of crank, J. B. Stanwood..... 359,280  
Shears. See Sheep shears.  
Sheep shears, F. Frielingshaus..... 359,232  
Shingle and making the same, wooden, B. J. Johnson..... 359,571  
Shoe lace fastening, H. B. Ten Eyck..... 359,477  
Shoulder pad, E. Goldman..... 359,441  
Signal. See Railway signal.  
Skate fastener, E. H. Barney..... 359,452  
Skimmer, telescopic, P. L. Kimball..... 359,510  
Sled propeller, F. F. Foster..... 359,504  
Sleeve protector, H. Smaadback..... 359,340  
Snap hook, C. H. Smith..... 359,407  
Snap hook, A. N. Sperry..... 359,406  
Spindle. See Spinning spindle.  
Spinning spindle and support therefor, J. Booth..... 359,542  
Spool holder, W. P. Clarke..... 359,430  
Spool or bobbin, enameled, S. D. Keane..... 359,447  
Spring. See Ambulance spring. Car spring.

|  |         |
|--|---------|
| Squaring, leveling, etc., combination tool for, D. W. Warren               | 350,372 |
| Stage effects, apparatus for producing, G. W. Davis                        | 350,248 |
| Stamps and labels, apparatus for applying postage, G. Phillips             | 350,326 |
| Station indicator, H. L. Shidder   | 350,329 |
| Steam boiler, J. A. Caldwell   | 350,358 |
| Steam generator, J. B. Stanwood  | 350,353 |
| Stethoscope, F. M. Blodgett  | 350,352 |
| Stopper. See Bottle stopper.   |         |
| Stove, T. Burkhard   | 350,314 |
| Stove, E. Butler   | 350,352 |
| Stove board, A. I. Griggs  | 350,353 |
| Stovepipe shelf, N. Linsley  | 350,374 |
| Sucker rod elevator, C. C. Stover  | 350,291 |
| Supporter. See Garment supporter.  |         |
| Surface and marking gauge, combined, E. Walker                             | 350,356 |
| Suspension hook, G. W. McGill  | 350,324 |
| Switch. See Telephone switch.  |         |
| Table. See Adjustable table. Metallic table.                               |         |
| Table, D. Mitchell   | 350,487 |
| Table leaf support, O. Colvin  | 350,432 |
| Table leaf support, Kaufhold & Genter                                      | 350,322 |
| Tanning and other purposes, treatment of hides and skins for, E. P. Nesbit | 350,360 |
| Tea or coffee pot, F. C. Taylor  | 350,282 |
| Telegraph system, police, Mehren & Carroll                                 | 350,575 |
| Telephone cabinet, C. Balloch  | 350,492 |
| Telephone register, C. Wittenberg  | 350,507 |
| Telephone switch, C. A. Hitchcock  | 350,356 |
| Telephone toll collectors, return attachment for, C. Wittenberg            | 350,306 |
| Temperature, electrical apparatus for regulating, C. W. Johnson            | 350,392 |
| Thill coupling, I. C. Hart   | 350,387 |
| Tie. See Railway tie.  |         |
| Time lock, C. H. Shaffer   | 350,549 |
| Tire bender, H. B. Kelper  | 350,509 |
| Tire coupling, wagon, J. J. Pinkham  | 350,361 |
| Toaster, T. W. Ball  | 350,417 |
| Toboggan, W. G. Shepard  | 350,406 |
| Tuol handle, G. D. Mosher  | 350,400 |
| Torpedo boat, electric, H. M. Bennett                                      | 350,313 |
| Trap. See Mole trap.   |         |
| Trellis, C. Schwend  | 350,547 |
| Tube. See Pneumatic dispatch tube.   |         |
| Tubes, screw cap for collapsible, H. M. Wirs                               | 350,305 |
| Type writing machines, copy holder for, A. S. Pattison                     | 350,495 |
| Umbrella, K. J. Colby  | 350,431 |
| Urinal, J. H. Stevens  | 350,334 |
| Valve, tubular well, N. E. Hildreth  | 350,444 |
| Vehicle, C. L. Peirce  | 350,498 |
| Vehicle fender, B. M. Stivers  | 350,476 |
| Vehicle wheel, W. C. Hodnett   | 350,445 |
| Vehicles, mud fender for, G. W. Atkins                                     | 350,580 |
| Wagon box, F. Fisher   | 350,436 |
| Warp threads, machine for drawing in, L. P. Sherman                        | 350,471 |
| Wash bench, folding, F. Hanson   | 350,565 |
| Washing machine, J. W. Roberts   | 350,519 |
| Washing machine, J. M. Shoaf   | 350,472 |
| Washing machine, G. H. Waldo   | 350,479 |
| Washing purposes, hand rubber for, McGovern & Hewitt                       | 350,368 |
| Watch case pendant, E. F. Margot   | 350,397 |
| Watch pinion cutting machine, E. A. Marsh                                  | 350,323 |
| Water closets, flushing apparatus for, W. H. Newell                        | 350,461 |
| Weighing machine, automatic grain, Weber & Harrison                        | 350,535 |
| Wheat and analogous grain, machine for reducing, Wilcox & Phillips         | 350,595 |
| Wheel. See Car wheel. Vehicle wheel. Wind wheel.                           |         |
| Whip socket, G. P. Rose  | 350,286 |
| Wind engine, H. J. Philpott  | 350,282 |
| Wind wheel, S. H. Heatwole   | 350,443 |
| Winding bobbins, attachment for, J. Pappa                                  | 350,277 |
| Window, J. S. Pihlstrom  | 350,383 |
| Wire basting machine, O. J. Ziegler  | 350,485 |
| Wire fastener, W. Orr  | 350,463 |
| Wire, machine for automatically forming rings from, J. Add                 | 350,416 |
| Wire rope machine, J. B. Stone   | 350,409 |
| Wire ropes, manufacturing, J. B. Stone                                     | 350,410 |
| Wire stretcher, H. M. Beckley  | 350,312 |
| Wood, composition for preserving, Brisley & Finch                          | 350,284 |
| Woodworking machine, A. D. Lina  | 350,453 |

## DESIGNS.

|   |        |
|---|--------|
| Ash receiver, J. G. Lyon                  | 17,181 |
| Collar, detachable, L. Robinson           | 17,158 |
| Corsets, ornamentation of, C. A. Griswold | 17,179 |
| Dish, T. B. Atterbury                     | 17,122 |
| Hat rack, hall, T. Hertwig                | 17,180 |
| Knit fabric, J. H. Osborne                | 17,193 |
| Moulding, F. Mankey                       | 17,182 |
| Panel, F. Mankey                          | 17,183 |
| Pulley, R. Osterhorn                      | 17,187 |
| Railway rail, Wharton, Jr., & Samuel      | 17,190 |
| Ring, A. Petzold                          | 17,196 |
| Steam radiator, hot closet, C. Rohlfis    | 17,197 |
| Tableware, J. E. Miller                   | 17,186 |
| Trimming, H. Rosenthal                    | 17,189 |

## TRADE MARKS.

|  |        |
|--|--------|
| Boots and shoes, L. Meyer  | 14,168 |
| Box handle, corrugated steel, J. K. Barton   | 14,163 |
| Corsets, L. S. H. Rosenberg  | 14,171 |
| Dermal emollient, A. G. Wilbur & Co  | 14,174 |
| Finger rings, Sinnock & Sherrill   | 14,172 |
| Grease or tallow for lubricating purposes, J. Williams   | 14,175 |
| Lintment, A. B. De Grath   | 14,164 |
| Lotion for the skin, Garver Drug Co  | 14,165 |
| Saddlery hardware, harness trimmings, harness leather, horse blankets, sheets, fly nets, and whips, E. S. Luqueer & Co | 14,167 |
| Soap for laundry, toilet, and general purposes, Oberste, Hosick & Co   | 14,170 |
| Tobacco, plug, Kurtz Bros  | 14,166 |
| Troches and cough balsam, M. R. Mulford  | 14,169 |
| Whisky, E. M. Tullmann   | 14,173 |

A printed copy of the specification and drawing of any patent in the foregoing list, also of any patent issued since 1867, will be furnished from this office for 25 cents. In ordering please state the number and date of the patent desired, and remit to Munn & Co., 361 Broadway, New York. We also furnish copies of patents granted prior to 1867; but at increased cost, as the specifications, not being printed, must be copied by hand.

Canadian Patents may now be obtained by the inventors for any of the inventions named in the foregoing list, provided they are simple, at a cost of \$40 each. If complicated the cost will be a little more. For full instructions address Munn & Co., 361 Broadway, New York. Other foreign patents may also be obtained.

## Advertisements.

Inside Page, each insertion --- 75 cents a line.  
Back Page, each insertion --- \$1.00 a line.  
The above are charges per agate line—about eight words per line. This notice shows the width of the line, and is set in agate type. Engravings may head advertisement at the same rate per agate line, by measurement, as the letter press. Advertisements must be received at publication office as early as Thursday morning to appear in next issue.



ORIGINAL ACCIDENT  
Company of America,  
LARGEST IN THE WORLD.

ALSO,  
Best of Life Companies.

Accident Policies, only \$5 per year to Professional, fessional and Business Men, for each \$1000, with \$15 Weekly Indemnity.

Accident Tickets, 25 cents per day, \$4.50 for 30 days, for Sale at all Local Agencies and Leading Railroad Stations.

ALSO THE  
Best Life Policy in the market. Indefeasible, Non-forfeitable, World-wide.

Paid Policy Holders, \$13,000,000.

Pays ALL CLAIMS Without Discount, and immediately upon receipt of satisfactory proofs.

Assets, . . . \$9,111,000  
Surplus, . . . \$2,129,000

JAMES C. BATTERSON, RODNEY DENNIS,  
President. Secretary.  
JOHN E. MORRIS, Asst Sec'y.

BIT. Square, Oval, or Round Smooth Holes For carpenter, cabinet, and pattern work. 1/2 in. to 2 in., set \$4.00, mailed free. Bridgeport Gun Implement Co., 17 Maiden Lane, N. Y.

Corrugated Copper Gaskets (patented), used in place of rubber or other destructible packings for connecting flange pipes, cylinder heads, steam chests, etc. This gasket is not injured by steam, oil, or acid solutions. U. S. Mineral Wool Company, 22 Cortlandt St., N. Y.

COUNTERSINK and DRILL COMBINED.



The Countersink following the Drill, the job is finished at one operation, saving the adjusting of tools and work twice. Made by Wiley & Russell Mfg. Co., Greenfield, Mass.

TIGHT & SLACK BARREL MACHINERY A SPECIALTY JOHN GREENWOOD & CO. ROCHESTER N.Y.

PERFECT  
NEWSPAPER FILE

The Koch Patent File, for preserving newspapers, magazines, and pamphlets, has been recently improved and price reduced. Subscribers to the SCIENTIFIC AMERICAN and SCIENTIFIC AMERICAN SUPPLEMENT can be supplied for the low price of \$1.50 by mail, or \$1.25 at the office of this paper. Heavy board sides; inscription SCIENTIFIC AMERICAN, in gilt. Necessary for every one who wishes to preserve the paper. Address

MUNN & CO.,  
Publishers SCIENTIFIC AMERICAN.

BARREL, KEG,  
Hogshead,  
AND  
STAVE MACHINERY.  
Over 50 varieties manufactured by  
Truss Hoop Driving. E. & B. Holmes,  
BUFFALO, N. Y.

The STATUE OF LIBERTY, NEW YORK.  
The great work of Bartholdi, the largest statue ever erected by man, just inaugurated on Bedloe's Island, New York Harbor, fully described. The history of its inception, how the work was carried out, chronology of the operations and full engineering and popular details as to construction, mode of erection, size, thickness of metal, etc. Fully illustrated by drawings, showing the work as completed, the elevation of the pedestal and framework, and the statue as it appeared in process of construction. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 524. Price 10 cents. To be had on application, or by mail, at this office and from all newsdealers.

WE WILL PAY agents a salary of \$85 per month and expenses to sell our goods to dealers, at home or to travel, or \$40 a month to distribute circulars in your vicinity. All expenses advanced. Salary promptly paid. Agents sample cases of goods FREE. No stamps required. No hunting. We mean what we say. Address MONARCH NOVELTY CO., Limited, CINCINNATI, OHIO.

SEBASTIAN, MAY & CO'S  
Improved Screw Cutting  
Foot & Power  
LATHES \$50.  
Drill Presses, Chucks, Drills, Dogs, and machinists' and amateurs' outfits. Catalogues mailed on application.  
165 W. 2d St., Cincinnati, O.

EXCELLENT BLACK COPIES of anything written or drawn with any Pen (or Type Writer) by the Patent Only equalled by Lithography. Specimens Free.  
AUTOCOPYIST CO., 5 Thomas Street, New York.

A firm in Austria, of old and highly respectable standing, wants for Importation to Austria Novelties in Technical Manufactures of every kind, such as Machinery in general, Utensils, Machinery for Working Men and Manufacturers, etc., for Industrial Establishments, Railroads, Mines, etc. Please address offers, catalogues and price lists to 134-136, rue Rudolf Mosse, Vienna, Austria.

ELECTRICAL. Edward P. Thompson, Solicitor of Electrical Patents, 3 Beekman Street, N. Y. Write for testimonials and instructions.

Syracuse Malleable Iron Works

2d HAND MACHINERY  
List sent. N. Y. Machinery Depot, Bridge Store No. 16, Frankfort Street, N. Y.

DEAF.—A very interesting 80-page book on Deafness, Noises in the Head, &c. How relieved. Sent free. Address NICHOLSON, 177 Macdougal St., N. Y.

Caligraph.  
LIFE SHORT—WRITE THE LONG WAY.  
Address: The American Writing Machine Co., Hartford, Conn.; New York Office, 237 Broadway.

GEO. W. MARBLE, Sole Manufacturer of THE ACME WRENCH.  
The best made, all steel, and warranted, 5 sizes. 25 to 32 South Canal Street, Chicago, U. S. A.

PLUMBER'S TRAP. State Rights of Patent No. 340,777, dated April 27, 1886, for sale. See page 153, Scientific American, March 12, 1887. Address F. C. & C. S. Gerstenberg, No. 1107 First Avenue, New York City.

SPECIAL MACHINERY  
For Grinding and Polishing  
Manufactured by The Somersworth Machine Co.,  
E. R. WARE, Agt.,  
154 Lake Street, CHICAGO.

Write for Circulars.

A NEW MAGAZINE—THE SWISS CROSS  
Devoted to spreading a love of nature among the people. Edited by HARLAN H. BALLARD, President of the Arctis Association, and succeeding St. Nicholas as the official magazine of that body. \$1.50 a year. Sample copy 10 cents, or 25 cents for trial subscription for 3 months.  
N. D. C. HODGES, PUBLISHER.  
Mention this paper. 47 Lafayette Place, New York.

\$90 a Month Salary to agents selling goods to dealers. Samples Free. \$40 a month to distribute circulars. Expenses advanced. National Supply Co., Cincinnati, O.

LINDHOLM & PETERSON, of Franconia, Minn., together with leading capitalists of McPherson, Kansas, have formed a corporation, with a working capital of \$20,000, for the manufacture and sale of Lindholm's Adding Machine. The corporation to be known as "The Lightning Adding Machine Co." of McPherson, Kansas, and all correspondence in regard to said Machine should be addressed as above.

CLARK'S NOISELESS RUBBER WHEELS  
No more Splintered Floors.  
Different Styles. Catalogue Free.  
GEO. P. CLARK,  
Box L. Windsor Locks, Ct.

Asbestos FELT WORKS, 101 Maiden Lane, N. Y., M. F. Adams, President and HARRIS FELT, Boiler and Pipe Coverings. Asbestos materials of all kinds m'td and applied. Estimates given.

CARY & MOEN  
STEEL WIRE OF EVERY DESCRIPTION  
234 W. 29 ST. EVERY STEEL SPRINGS, NEW YORK CITY

PLAY THE PIANO AND ORGAN  
By using Soper's Instantaneous Guide, any person can play a tune on either instrument at once without the aid of a teacher. No previous knowledge of music whatever required. Send for book of testimonials free. Address G. K. HEARNE & CO., P. O. Box 167, New York.

Telegraph and Electrical SUPPLIES  
Medical Batteries, Inventors' Models, Experimental Work, and fine brass castings. Send for catalogue C. E. JONES & BRO. Cincinnati, O. It is important to us that you mention this paper.

JET PROPELLERS.—A DISCUSSION OF the efficiency of jet propellers for the hydraulic propulsion of vessels, as compared with the screw. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 561. Price, 10 cents. To be had at this office and from all newsdealers.

To Business Men.

The value of the SCIENTIFIC AMERICAN as an advertising medium cannot be overestimated. Its circulation is many times greater than that of any similar journal now published. It goes into all the States and Territories, and is read in all the principal libraries and reading rooms of the world. A business man wants something more than to see his advertisement in a printed newspaper. He wants circulation. This he has when he advertises in the SCIENTIFIC AMERICAN. And do not let the advertising agent influence you to substitute some other paper for the SCIENTIFIC AMERICAN, when selecting a list of publications in which you decide it is for your interest to advertise. This is frequently done, for the reason that the agent gets a larger commission from the papers having a small circulation than is allowed on the SCIENTIFIC AMERICAN.  
For rates see top of first column of this page, or address  
MUNN & CO., Publishers,  
361 Broadway, New York.

- THE -

Scientific American  
Building Edition.

THE SCIENTIFIC AMERICAN ARCHITECTS' AND BUILDERS' EDITION is issued monthly. \$3.50 a year. Single copies, 25 cents. Forty large quarto pages, equal to about two hundred ordinary book pages; forming, practically, a large and splendid Magazine of Architecture, richly adorned with elegant plates in colors, and with fine engravings; illustrating the most interesting examples of modern Architectural Construction and allied subjects.

A special feature is the presentation in each number of a variety of the latest and best plans for private residences, city and country, including those of very moderate cost as well as the more expensive. Drawings in perspective and in color are given, together with full Plans, Specifications, Costs, Bills of Estimate, and Sheets of Details.

Architects, Builders, and Owners will find this work valuable in furnishing fresh and useful suggestions. All who contemplate building or improving homes or erecting structures of any kind, have before them in this work an almost endless series of the latest and best examples from which to make selections, thus saving time and money.

Many other subjects, including Sewerage, Piping, Lighting, Warming, Ventilating, Decorating, Laying Out of Grounds, etc., are illustrated. An extensive Compendium of Manufacturers' Announcements is also given, in which the most reliable and approved Building Materials, Goods, Machines, Tools, and Appliances are described and illustrated, with addresses of the makers, etc.

The fullness, richness, cheapness, and convenience of this work have won for it the Largest Circulation of any Architectural publication in the world. Sold by all newsdealers.

MUNN & CO., Publishers,  
361 Broadway, New York.

## Building Plans and Specifications.

In connection with the publication of the BUILDING EDITION of the SCIENTIFIC AMERICAN, Messrs. Munn & Co. furnish Plans and Specifications for Buildings of every kind, including Public Buildings, Churches, Schools, Stores, Dwellings, Carriage Houses, Barns, etc. In this work they are assisted by able and experienced architects.

Those who contemplate building, or who wish to alter, improve, extend, or add to existing buildings, whether wings, porches, bay windows, or attic rooms, are invited to communicate with the undersigned. Our work extends to all parts of the country. Estimates, plans, and drawings promptly prepared. Terms moderate. Address  
MUNN & CO., 361 Broadway, New York.

ROP HAMMERS  
Punching Presses  
DIES AND OTHER TOOLS  
Branch Office and Factory, 20 Center Street, New York.

TIMBER GAINING MACHINE.  
Special Machinery for Car Work and the latest improved Wood Working Machinery of all kinds.  
C. B. Rogers & Co.,  
New York, Conn.  
109 Liberty Street, New York.

SILK RIBBONS!  
We have purchased at recent wholesale auction sales several large lots of Remnants of Silk Ribbons at prices which will enable us to offer splendid bargains. These remnants are all from two to three yards and upwards in length, and many of them are the finest quality of Ribbons in the market, of different widths, in a variety of fashionable shades, in fact, nearly all colors are represented; also different kinds of Ribbons adapted for bonnet strings, neckwear, trimming for hats and dresses, bows, scarfs, etc., etc. No lady can purchase such fine ribbons as these at any store in the land for four times the money. If you will agree to show the goods to friends, and aid us in making sales, we will send a sample box of these elegant ribbons for 25 cents in stamps. Two boxes 50 cts. Four boxes \$1.00. Ten boxes \$2.50. Address PARIS AGENCY, 7 West Broadway, New York.

THE ONLY PRACTICAL ELECTRIC MOTORS FOR FAMILY, BUSINESS, MANUFACTURING, AND AGRICULTURAL PURPOSES.  
224 ARTER STREET, PHILA. PA.

## Two Very Important Books FOR ARTISANS AND AMATEURS. Lately Published.

**VARNISHES, LACQUERS, ETC.**  
The only one now in print in the English Language.

A Practical Treatise on the Fabrication of Varnishes and Lacquers. From the German of Erwin Andres, Manufacturer of Varnishes and Lacquers. With additions on the Manufacture and Application of Varnishes, Stains for Wood, Horn, Ivory, Bone, and Leather. From the German of Dr. Emil Winkler and Louis E. Andres. The whole translated and edited by William T. Brant, Graduate of the Royal Agricultural College of Eldon, Prussia. Illustrated. In one volume, 366 pages, 12mo. Price, \$2.50. Sent by mail, free of postage, to any address in the world.

A Practical Book for Every One.

## THE FABRICATION OF Glue, Gelatine, Gelatine Veneers, AND Folio, Isinglass, Cements, Pastes, and Mucilages.

A Practical Treatise on the Raw Materials and Fabrication of Glue, Gelatine, Gelatine Veneers, and Folio, Isinglass, Cements, Pastes, Mucilages, etc., based upon actual experience, by F. Danilowsky, Technical Chemist. Translated from the German, with extensive additions, including a description of the most recent American processes, by Wm. T. Brant. Illustrated by 35 engravings. 12mo. Price, \$2.50.

The above or any of our Books sent by mail, free of postage, at the publication price, to any address in the world.

Our new and enlarged Catalogue of Practical and Scientific Books, 96 pages, 8vo, and our other Catalogues, the whole covering every branch of Science Applied to the Arts, sent free and free of postage to any one in any part of the World who will furnish us with his address.

**HENRY CAREY BAIRD & CO.,**  
INDUSTRIAL PUBLISHERS, BOOKSELLERS & IMPORTERS  
810 Walnut Street, Philadelphia, Pa., U. S. A.

## The Techno-Chemical Receipt Book: NOW READY.

## The Techno-Chemical Receipt Book.

Containing Several Thousand Receipts, covering the latest, most important, and most useful Discoveries in Chemical Technology, and their Practical Application in the Arts and Industries. Edited chiefly from the German of Drs. Winkler, Eisner, Heintze, Mierszinski, Jacobsen, Koller, and Heinzel, with additions by William T. Brant, Graduate of the Royal Agricultural College of Eldon, Prussia, and William H. Wahl, Ph. D. (Held.), Secretary of the Franklin Institute, Philadelphia, author of "Galvanoplastic Manipulations." Illustrated by 75 engravings, in one volume, over 500 pages, 12mo, closely printed, containing an immense amount and a great variety of matter. Elegantly bound in scarlet cloth, gilt. Price \$2.50, free of postage to any address in the world.

A circular of 32 pages, showing the full Table of Contents of this important Book, sent by mail, free of postage to any one in any part of the World who will furnish us with his address.

**HENRY CAREY BAIRD & CO.,**  
Industrial Publishers, Booksellers, and Importers,  
810 Walnut St., Philadelphia, Pa., U. S. A.

**PATENT FOR SALE. THE ADAMSON CO.,**  
Patent Solicitors, Munich, Ind.

**THE COPYING PAD.—HOW TO MAKE**  
and how to use; with an engraving. Practical directions how to prepare the gelatine pad, and also the aniline ink by which the copies are made; how to apply the written letter to the pad; how to take off copies of the letter. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 438. Price 10 cents. For sale at this office and by all newsdealers in all parts of the country.

## THE DINGEE & CONARD CO'S BEAUTIFUL EVER-BLOOMING ROSES

For 18 Years our Great Specialty has been growing and distributing ROSES. We have all the latest varieties and most standard ones in different sizes and prices to suit all. We send STURGE, VIGOR, OUR PLANTS safely by mail or express to all points, 3 TO 12 PLANTS \$1.50 to \$2.50. Our New Guide, 88 pp., describes nearly 500 finest varieties of Roses, the best Hardy Shrubs, & Climbing Vines, and New and Rare Flower Seeds, and tells how to grow them—FREE. Address THE DINGEE & CONARD CO., Rose Growers, West Grove, Chester Co., Pa.



## MARVELOUS MEMORY DISCOVERY.


Wholly unlike Artificial Systems—Cure of Mind Wandering. Any book learned in one reading. Great inducements to Correspondence Classes. Prospectus, with opinions in full of Mr. RICHARD A. PROCTOR, Hon. W. W. ASTOR, JUDAH P. BENJAMIN, DR. MINOR, WOOD, REV. FRANCIS B. DENIO, MARK TWAIN, and others, sent post free by  
**PROF. LOISETTE,**  
237 Fifth Avenue, New York.

## CURE FOR THE DEAF

FREE'S PATENT IMPROVED CUSHIONED EAR DRUMS Perfectly restore the Hearing, and perform the work of the natural drum. Invaluable, comfortable and always in position. All conversation and even whispers heard distinctly. Send for illustrated book with testimonials, FREE. Address or call on F. FREE, 853 Broadway, New York. Mention this paper.

**DEAFNESS** Its causes, and a new and successful CURE at your own home, by one who was deaf twenty-eight years. Treated by most of the noted specialists without benefit. Cured himself in three months, and since then hundreds of others. Full particulars sent on application.  
T. S. PAGE, No. 41 West 31st St., New York City.

**PILES** Instant relief. Final cure and never returns. No incision. Neither knife, purgative, or suppository. Liver, kidney and all bowel troubles—especially constipation—cured like magic. Sufferers will learn of a simple remedy free, by addressing, J. H. RILEY, 78 Nassau St., N. Y.



## RICE AUTOMATIC CUT-OFF ENGINE.

Self-Contained, Sensitive Governor.  
Balanced Valve, High Speeds.  
Stationary Oilers, Best Economy.

Gold Medal Cincinnati Exposition, 1884.

**THE JOHN T. NOYE MFG. CO.,**  
BUFFALO, N. Y.

## OIL WORKS MACHINERY

HYDROSTATIC PRESSES,  
ENGINES, BOILERS, CASTINGS  
WM. TAYLOR & SONS,  
23-39 Adams St., Brooklyn, N. Y.

RAILWAY AND STEAM FITTERS' SUPPLIES  
Rue's Little Giant Injector.

SCREW JACKS, STURTEVANT BLOWERS, &c.  
JOHN S. URQUHART, 46 Cortlandt St., N. Y.

**INFORMATION**  
For Users of Steam Pumps.  
Van Duzen's Patent Steam Pump  
Requires No Packing or Oil.  
Requires No Repairs or Skill.  
Can pump any kind of liquid; ever ready; no moving parts; all brass; cannot clog nor get out of order; fully tested; hundreds in daily use; every pump guaranteed; not like cheap pumps made of iron; all sizes to 8 inch discharge; prices from \$7 upward; capacities from 100 to 30,000 gallons per hour. State for what purpose wanted and send for Catalogue of "Pumps."  
VAN DUZEN & TIFT, Cincinnati, O.

**PROSPECTING MINERAL LANDS A SPECIALTY.**  
CYLINDRICAL SECTION OR CORES OBTAINED THE WHOLE DISTANCE BORED.  
**ARTESIAN WELLS**  
BORED ROUND AND STRAIGHT  
ADMITTING A LARGER PUMP & CASING IN PROPORTION TO SIZE OF HOLE THAN BY ANY OTHER PROCESS. ESTIMATES GIVEN AND CONTRACTS MADE BY  
**THE PENNSYLVANIA DIAMOND DRILL CO.**  
BIRDSBORO PA.  
MANUFACTURERS OF DIAMOND DRILLS FOR ALL KINDS OF ROCK BORING.

**ROCK BREAKERS AND ORE CRUSHERS.**  
We manufacture and supply at short notice and lowest rates, Stone and Ore Crushers, containing the invention described in Letters Patent issued to Eli W. Blake, June 15th, 1884, together with NEW AND VALUABLE IMPROVEMENTS, for which Letters Patent were granted May 11th and July 20th, 1886, to Mr. S. L. Marsden. All Crushers supplied by us are constructed under the superintendence of Mr. Marsden, who, for the past twenty years, has been connected with the manufacture of Blake Crushers in this country and England.  
**FARREL FOUNDRY AND MACHINE CO.,** Manufacturers, Ansonia, Conn.  
**COPELAND & BACON, Agents, NEW YORK.**

Shafting and Gearing, Textile Machinery, THOS. WOOD & CO.  
ELEVATORS, ETC. 22d and Wood Sts., Philadelphia, Pa.

## OTTO GAS ENGINE.

GUARANTEED TO CONSUME 25 TO 75 PER CENT. LESS GAS THAN ANY OTHER GAS ENGINE DOING THE SAME WORK.  
SCHLEICHER, SCHUMM & CO. PHILADELPHIA AND CHICAGO.

**Barnes' Foot-Power Machinery.**  
Complete outfit for Actual Workshop Business. Read what a customer says: "Considering its capacity and the accuracy of your No. 4 Lathe, I do not see how it can be produced at such low cost. The velocipede foot-power is simply elegant. I can turn steadily for a whole day and at night feel as little tired as if I had been walking around." Descriptive Catalogue and Price List Free. W. F. & JOHN BARNES Co. Address 199 Main St., Rockford, Ill.

## EPPS'S GRATEFUL-COMFORTING. COCOA

**COMBUSTION, FIREBOXES AND**  
steam boilers. By John A. Coleman. Definition of combustion. What successful combustion requires. Furnace phenomena. The steam boiler. Locomotive boilers. The locomotive of the future. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 561. Price, 10 cents. To be had at this office and from all newsdealers.

**VOLNEY W. MASON & CO.,**  
FRICTION PULLEYS CLUTCHES AND ELEVATORS  
PROVIDENCE, R. I.

## Trade Secrets

"SECRET" Recipes, Formulas, etc., which have been advertised for sale. Edited with corrections and hints for improvements by a well-known Technologist. Neatly cloth bound, 60 cents by mail, or from any bookseller. Catalogue Scientific and Mechanical books free.  
J. H. PHIN, 15 Dey Street, New York.

## VULCANITE EMERY WHEELS.

Made SOLID of the Celebrated WELLINGTON MILLS EMERY.  
**SUPERIOR TO ALL OTHERS.**  
Thousands of manufacturers testify to its being the Strongest, most Durable, and Healthiest Emery Wheel made.  
**RUNS WET or DRY.**  
CUTS COOL and FREE.  
A SAFE WHEEL.  
**NEW YORK BELTING & PACKING CO.,**  
Sole Manufacturers.  
Warehouse: 15 Park Row, New York.



**ICE & REFRIGERATING**  
Machines. York Patent. YORK MFG. CO., York, Pa.



**INSURANCE CO. OF HARTFORD CONN.**  
CASH CAPITAL \$4,000,000  
LOSSES PAID IN 67 YEARS \$58,750,000  
The Largest and Strongest Company.  
L. J. HENDEL, President, WM. B. CLARK, Asst. Sec'y

**RADII OF CURVATURE GEOMETRICAL**  
ly considered. By Prof. C. W. MacCord. Explanation of a new method of determining the radii of curvature of many plane curves by very simple graphic constructions; the mode of operation being based upon the fundamental ideas of regarding a line as generated by the motion of a point, the tangent as the direction of that motion at a given instant, and the normal as a line also in motion, with 22 figures. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, Nos. 537, 538, 539, 540, 541, 542 and 547. Price, 10 cents each, or 60 cents for the series. To be had at this office or from any newsdealer.

## THE UNIVERSAL FLY CATCHER.

A remarkable fly trap has been perfected that will supersede all other fly traps and fly papers, and keep any house free from flies. Patented in United States, Canada, England, France, Belgium, Germany, Austria, Spain, State rights and foreign patents for sale. See advt. in April, 87, Sci. Am. BUILDERS' EDITION, page 11. Address with stamp, Z. XEVERS, 205 Brannon St., San Francisco, Cal.

**W E L L**  
Encyclo- Diamond Book free, s-  
pedia of Drills and sec. for  
700 Engrav- and Light- mailing  
ings of Hy- ning it.  
WELL, WELL, American  
TOOLS, MACHINES, Well Works,  
Aurora, Ill.

## PROSPECTUS OF THE Scientific American FOR 1887.

The Most Popular Scientific Paper in the World.  
Only \$3.00 a Year, including Postage. Weekly.  
32 Numbers a Year.

This widely circulated and splendidly illustrated paper is published weekly. Every number contains sixteen pages of useful information and a large number of original engravings of new inventions and discoveries, representing Engineering Works, Steam Machinery, New Inventions, Novelties in Mechanics, Manufactures, Chemistry, Electricity, Telegraphy, Photography, Architecture, Agriculture, Horticulture, Natural History, etc.

All Classes of Readers find in the SCIENTIFIC AMERICAN a popular resume of the best scientific information of the day; and it is the aim of the publishers to present it in an attractive form, avoiding as much as possible abstruse terms. To every intelligent mind, this journal affords a constant supply of instructive reading. It is promotive of knowledge and progress in every community where it circulates.

**Terms of Subscription.**—One copy of the SCIENTIFIC AMERICAN will be sent for one year—32 numbers—postage prepaid, to any subscriber in the United States or Canada, on receipt of three dollars by the publishers; six months, \$1.50; three months, \$1.00.

**Clubs.**—One extra copy of the SCIENTIFIC AMERICAN will be supplied gratis for every club of five subscribers at \$3.00 each; additional copies at same proportionate rate.

The safest way to remit is by Postal Order, Draft, or Express Money Order. Money carefully placed inside of envelopes, securely sealed, and correctly addressed, seldom goes astray, but is at the sender's risk. Address all letters and make all orders, drafts, etc., payable to

**MUNN & CO.,**  
361 Broadway, New York.

## THE Scientific American Supplement.

This is a separate and distinct publication from THE SCIENTIFIC AMERICAN, but is uniform therewith in size, every number containing sixteen large pages. THE SCIENTIFIC AMERICAN SUPPLEMENT is published weekly, and includes a very wide range of contents. It presents the most recent papers by eminent writers in all the principal departments of Science and the Useful Arts, embracing Biology, Geology, Mineralogy, Natural History, Geography, Archaeology, Astronomy, Chemistry, Electricity, Light, Heat, Mechanical Engineering, Steam and Railway Engineering, Mining, Ship Building, Marine Engineering, Photography, Technology, Manufacturing Industries, Sanitary Engineering, Agriculture, Horticulture, Domestic Economy, Biography, Medicine, etc. A vast amount of fresh and valuable information pertaining to these and allied subjects is given, the whole profusely illustrated with engravings.

The most important Engineering Works, Mechanisms, and Manufactures at home and abroad are represented and described in the SUPPLEMENT.

Price for the SUPPLEMENT for the United States and Canada, \$5.00 a year, or one copy of the SCIENTIFIC AMERICAN and one copy of the SUPPLEMENT, both mailed for one year for \$7.00. Address and remit by postal order, express money order, or check.

**MUNN & CO., 361 Broadway, N. Y.,**  
Publishers SCIENTIFIC AMERICAN.

**To Foreign Subscribers.**—Under the facilities of the Postal Union, the SCIENTIFIC AMERICAN is now sent by post direct from New York, with regularity, to subscribers in Great Britain, India, Australia, and all other British colonies; to France, Austria, Belgium, Germany, Russia, and all other European States; Japan, Brazil, Mexico, and all States of Central and South America. Terms, when sent to foreign countries, Canada excepted, \$4.00, for SCIENTIFIC AMERICAN and SUPPLEMENT for one year. This includes postage, which we pay. Remit by postal or express money order, or draft to order of  
**MUNN & CO., 361 Broadway, New York.**

## Advertisements.

Inside Page, each insertion --- 75 cents a line.  
Back Page each insertion --- \$1.00 a line.  
The above are charges per square line—about eight words per line. This notice shows the width of the line, and is set in agate type. Engravings may be advertised at the same rate per square line, by measurement, as the letter press. Advertisements must be received at publication office as early as Thursday morning to appear in next issue.

## AQUA PURA


BY NATURE'S PROCESSES  
Turbid Water Made Clean.  
Matter in Suspension and ORGANIC and Semi-Soluble Elements removed.  
Hard Water Made Soft.  
Cities, Towns, Mills, Hotels, and Private Houses Supplied and Residuals Guaranteed.  
Scale in Boilers Avoided.  
Two per cent. added to the Annual Water Rates in any city will give the people PERFECT WATER for all time.

Send for Circulars and Estimates.  
NEWARK FILTERING CO., NEWARK, N. J.  
TRINITY BUILDING, NEW YORK.



Send \$1. for sample, by mail. Utility French Co., 221 East Ninth Street, New York City, U. S. A.

DRIVING-BELTS.—A PAPER BY John Tullis, discussing the comparative value of various kinds of belting. Main driving-belts. Patent leather chain belting. Half-twist belts. Cotton belts. Leather ropes. With 8 engravings. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 302. Price 10 cents. To be had at this office and from all newdealers.



Samples and Illustrated Pamphlet "Steam Saving and Fire-Proof Materials" Free by Mail.  
H. W. JOHNS MANUFACTURING CO.,  
SOLE MANUFACTURERS OF

H. W. Johns' Fire and Water-Proof Asbestos Roofing, Sheathing, Building Felt, Asbestos Steam Packings, Boiler Coverings, Roof Paints, Fire-Proof Paints, etc.  
VULCABESTON, Moulded Piston-Rod Packing, Rings, Gaskets, Sheet Packing, etc.  
Established 1858. 87 MAIDEN LANE, NEW YORK. CHICAGO, PHILADELPHIA, LONDON.

## JENKINS BROS. VALVES.

THE ENDORSEMENT OF FIRST-CLASS ENGINEERS AND MECHANICS THROUGHOUT THE COUNTRY has fully demonstrated these valves to possess the following advantages over all other valves now in use:  
1. A perfectly tight valve under any and all pressures of steam, oils, or gases.  
2. Sand or grit of any kind will not injure the seat.  
3. You do not have to take them off to repair them.  
4. They can be repaired by any mechanic in a few minutes.  
5. The elasticity of the Disc allows it to adapt itself to an imperfect surface.  
In Valves having ground or metal seats, should sand or grit get upon the seat, it is impossible to make them tight, except by regrinding, which is expensive if done by hand, and if done by machine soon wears out the valve, and in most cases they have to be disconnected from the pipes, often costing more than a new valve. The Jenkins Discs used in these valves are manufactured under our 1860 patent, and will stand any pressure of steam, oils, or acids.  
JENKINS BROS., 71 John St., N. Y.; 105 Milk St., Boston; 13 So. Fourth St., Phila.



## PATENTS.

MESSRS. MUNN & CO., in connection with the publication of the SCIENTIFIC AMERICAN, continue to examine improvements, and to act as Solicitors of Patents for Inventors.

In this line of business they have had forty-one years' experience, and now have unequalled facilities for the preparation of Patent Drawings, Specifications, and the prosecution of Applications for Patents in the United States, Canada, and Foreign Countries. Messrs. Munn & Co. also attend to the preparation of Caveats, Copyrights for Books, Labels, Reissues, Assignments, and Reports on Infringements of Patents. All business entrusted to them is done with special care and promptness, on very reasonable terms.

A pamphlet sent free of charge, on application, containing full information about Patents and how to procure them; directions concerning Labels, Copyrights, Designs, Patents, Appeals, Reissues, Infringements, Assignments, Rejected Cases, Hints on the Sale of Patents, etc.

We also send, free of charge, a Synopsis of Foreign Patent Laws, showing the cost and method of securing patents in all the principal countries of the world.  
MUNN & CO., Solicitors of Patents,  
361 Broadway, New York.

BRANCH OFFICES.—No. 622 and 624 F Street, Pacific Building, near 7th Street, Washington, D. C.  
PRINTING INKS.  
THE "Scientific American" is printed with CHAS. T. BURNETT & CO.'S INK. Tenth and Lombard Sts., Phila., and 47 Rose St., opp. Duane St., N. Y.

## THE AMERICAN BELL TELEPHONE CO.

95 MILK ST., BOSTON, MASS.

This Company owns the Letters Patent granted to Alexander Graham Bell, March 7th, 1876, No. 174,465, and January 30th, 1877, No. 186,787.

The transmission of Speech by all known forms of Electric Speaking Telephones infringes the right secured to this Company by the above patents, and renders each individual user of telephones not furnished by it or its licensees responsible for such unlawful use, and all the consequences thereof, and liable to suit therefor.

PATENT  
JACKET KETTLES,  
Plain or Porcelain Lined. Tested to 100 lb. pressure. Send for List.  
HAND, BURR & CO.,  
614 and 616 Market St., Philadelphia, Pa.

BEST and most RELIABLE for swift running.  
ELECTRIC LEATHER BELTING  
Chas. A. Schieren & Co.,  
47 Ferry St., New York.  
410 Arch St., Phila.  
86 Federal St., Boston.

PHOTOGRAPHS of Microscopic Objects, of Insects, Polycrystals, etc. For sample photograph and list of objects, send 25 cents to Frank A. Butler, 450 Lafayette Avenue, Brooklyn, N. Y.

COPPER TUBES  
SHEET BRASSWARE  
Mention this paper.

Remarkable Success!!  
DR. SCOTT'S GENUINE ELECTRIC BELTS

PRICE \$3.00 ON TRIAL



These Belts are for sale at drug stores, but if not in your immediate vicinity, send direct to Dr. SCOTT, 842 Broadway, New York.  
Each is stamped with the name Fall Mail Electric Ass'n of London.

Handsome Screen Belts at \$5.00.

## Dr. Scott's Electric Suspensory, the Genuine Article, \$5.

Intense nervous debility has been my trouble for years. Physicians and their medicines did not help me. I finally derived great relief from Dr. Scott's Electric Belt.  
Your Belt has cured me of Insomnia and nervousness, and has also had wonderful effect on Neurasthenia of the chest.  
R. SELL.  
Baltimore, Md.  
This Belt has done me more good in a short time than all the medicine I ever took.  
E. W. MEADE.  
Houston, Mich.  
Dr. Scott's Electric Belt has cured my brother of severe backache from which he has suffered eight years. My father, 70 years old, could not walk 100 yards; after wearing the Belt one month he walked nine miles without resting.  
Dr. Scott's Electric Corsets cure and prevent sickness. \$1, \$1.50, \$2, and \$3.  
DR. SCOTT'S ELECTRIC CHEST PROTECTOR, \$3.  
DR. SCOTT'S ELECTRIC HAIR BRUSHES, \$3.  
DR. SCOTT'S ELECTRIC INSOLES, 50 cts.  
10,000 agents wanted, quick sales, liberal pay, satisfaction guaranteed.

THE BRIDGEPORT WOOD FINISHING CO.  
G. M. BREINIG, AGENT, PRINCIPAL OFFICE AT MANUFACTORY NEW MILFORD, CONN.  
NEW YORK BUSINESS OFFICE, 96-98 MAIDEN LANE. MANUFACTURERS OF  
WHEELERS PATENT WOOD FILLER.  
BREINIG'S LITHOGEN SILICATE PAINT.  
LITHOGEN-PRIMER, WOOD STAINS  
SILEX FLINT AND FELDSPAR.  
PAMPHLET GIVING DIRECTIONS FOR FINISHING HARD WOOD FREE TO ANY ADDRESS.

## ELECTRICAL APPLIANCES.

HOW MADE AND HOW USED.  
This valuable book sent FREE to any address.  
HORACE VAN SANDS, 68 Broadway, New York.

## SAFES Fire and Burglar Proof

Safes for all purposes. Bank and Safe Deposit Vaults, Vault Doors, Ac. Estimates and drawings furnished.  
DIEBOLD SAFE AND LOCK COMPANY.  
W. H. BUTLER, Gen'l Agent, 79 Duane St., N. Y.



WE would call especial attention to the following articles now for the first time offered to the public, manufactured from this new material.

Vulcabeston, is composed of asbestos combined with water and acid proof materials vulcanized and compressed. It is manufactured exclusively by the JOHN-PRATT CO., of Hartford, Conn., of which we are the sole agents.

VULCABESTON is superior to any other known material on account of its permanent resistance to heat and immunity from injury by acids, gases, etc., and is therefore invaluable for a variety of purposes. It can be made in any desired form. At present we are prepared to supply Soft, Medium, and Hard SHEET PACKING, all thicknesses, in sheets 40x40 inches, MOULDED PISTON-ROD PACKING, MOULDED PISTON PACKING, GASKETS, RING FLANGE PACKINGS, WASHERS, etc.

## Vulcanized Asbestos Piston-Rod Packing.

This is a flexible rope packing composed of strong twisted strands of pure Asbestos combined with India Rubber and vulcanized. It is an improvement upon our Pure Asbestos Packings, and is superior to all others for piston-rods, valve-stems, pump valves, etc., where high pressure steam, hot water, oils, acids, ammonia, etc., are used, and for locomotives, stationary, and marine engines. The advantages possessed by this Packing are that, in consequence of its wonderful strength and durability, it can be used wherever metallic packings have been heretofore necessary. It is self-lubricating to a greater extent than any other material, and it will not shrink or blow out. Round and square, all sizes, from 1-8 inch to 2 inches in diameter.

Samples and Descriptive Price Lists free by mail.

H. W. JOHNS MANUFACTURING CO.,  
SOLE MANUFACTURERS OF  
H. W. Johns' Fire and Water-Proof Asbestos Sheathing and Building Felt, Asbestos Roofing and Roof Paints, Asbestos Steam Packings, Boiler Coverings, Liquid Paints, Fire-Proof Paints, etc.  
Established 1858. 87 MAIDEN LANE, NEW YORK. CHICAGO, PHILADELPHIA, LONDON.

SUPPLIES FROM  
HYDRANT PRESSURE  
the cheapest power known,  
valuable for blowing  
Church Organs, running  
Printing Presses, Sewing  
Machines in Households,  
Turning Lathes, Scroll  
Saws, Grindstones, Coffee  
Mills, Sausage Machines,  
Feed Cutters, Electric  
Lamps, Elevators, etc.  
It needs little room, no firing  
up, fuel, ashes, repairs, en-  
gineer, explosion, or delay,  
no extra insurance, no coal  
bills. Is noiseless, neat,  
compact, steady; will work  
at any pressure of water  
above 15 lb.; at 40 lb. pres-  
sure has 4-horse power, and  
capacity up to 1-horse  
power. Prices from \$15 to \$300. Send for circular to  
THE BACKUS WATER MOTOR CO., Newark, N. J.

BEFORE YOU BUY A BICYCLE  
OR GUN send stamp to A. W. GUMP,  
Dayton, Ohio, for new and second-hand  
price list. REPAIRING and NICKELING.  
SECOND-HAND BICYCLES, GUNS  
and REVOLVERS taken in EXCHANGE.

LEPAGE'S  
THE ONLY GENUINE  
LIQUID GLUE  
UNEQUALLED FOR CEMENTING  
wood, glass, china, paper, leather, etc. Always  
ready for use. Prepared and bottled by  
(IS MADE BY THE) LEPAGE BROS.  
Russia Cement Co., Gloucester, Mass.  
Sample 25c stamp

SCIENTIFIC AMERICAN SUPPLE-  
MENT. Any desired back number of the SCIENTIFIC  
AMERICAN SUPPLEMENT can be had at this office for  
10 cents. Also to be had of newdealers in all parts of  
the country.

THE WASHBURN AMERICAN GUITARS  
AND MANDOLINES  
Finest toned, most durable,  
and possess the only absolutely  
correct scale. Warranted to stand in any climate.  
Ask your dealer  
for them. Illustrated Catalogue mailed free by the Manufacturers,  
LYON & HEALY, 102 State St., Chicago.